<u>GENERAL NOTES</u>
1. TAX PARCEL NO.: 47-00-03758-00-2 BLOCK: 023 UNIT: 003 2. EXISTING SITE DATA: GROSS LOT AREA: 962,447.42 S.F.(22.09 AC) DEED INFORMATION: DBV. 5669 PG.00252 3. RECORD OWNER/SUBDIVIDER: 1150 FIRST AVE STE 920 KING OF PRUSSIA, PA 4. BOUNDARY AND TOPOGRAPHIC SURVEY INFORMATION PROVIDED BY MICHAEL DIPAOLO, PLS, FROM ACTUAL FIELD SURVEY PERFORMED MAY 5. SITE FALLS IN ZONE (X) BASED ON FEMA MAP NUMBER 42091C0083 E EFFECTIVE DATE: OCTOBER 19, 1996. • PLAN BY BURSICH ASSOCIATES INC. TITLED "SKETCH PLAN" DRAWING NUMBER 1 OF 1 DATED 09-12-07 LAST REVISED N/A. 7. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES, WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. 8. THE DATUM IS BASED ON LIDAR MAPPING. 9. INTENDED USE: THREE PROPOSED DETACHED DWELLINGS AND ONE EXISTING DETACHED DWELLING WITH ON LOT SEWER AND WATER. 10. SOURCE OF TITLE: BEING THE SAME PROPERTY OF FIRST PENN BANK BY DEED DATED OCTOBER 12TH, 2007 AND RECORDED IN DBV. 5669 PG. 00252, MONTGOMERY COUNTY RECORDS, GRANTED AND CONVEYED UNTO FDEV 11. THE TOWNSHIP SHALL BE GRANTED A BLANKET EASEMENT ON EACH LOT FOR INSPECTION OF THE PROPOSED STORMWATER FACILITIES. 12. SURVEY MONUMENTATION SHALL BE INSTALLED PER TOWNSHIP REQUIREMENTS. 13. INDIVIDUAL RAINGARDENS AND TRENCH DRAINS/OUTLET PIPES SHALL BE OWNED AND MAINTAINED BY THE RESPECTIVE LOT OWNERS. 14. CLEAR SIGHT TRIANGLES SHALL BE MAINTAINED, WITHIN WHICH VEGETATION AND OTHER VISUAL OBSTRUCTIONS SHALL BE LIMITED IN HEIGHT OF NOT MORE THAN 2' ABOVE STREET GRADE. 15. THREE PARKING SPACES SHALL BE PROVIDED FOR EACH LOT(2.25 REQUIRED). 16. THE DETENTION BASINS AND STORMWATER FACILITIES (AS SHOWN ON THIS PLAN) ARE A BASIC AND PERPETUAL PLAN OF THE STORM DRAINAGE SYSTEM OF THE TOWNSHIP OF NEW HANOVER, AND AS SUCH ARE TO BE PROTECTED AND PRESERVED, IN ACCORDANCE WITH THE APPROVED FINAL PLAN BY THE OWNER(S) ON WHOSE LANDS THE STRUCTURE(S) IS(ARE) LOCATED. THE TOWNSHIP OF NEW HANOVER AND/OR ITS AGENTS RESERVES THE RIGHT AND PRIVILEGE TO ENTER UPON SUCH LANDS FROM TIME TO TIME FOR THE PURPOSE OF INSPECTION OF SAID DETENTION BASIN(S) IN ORDER TO DETERMINE THAT THE STRUCTURAL AND DESIGN INTEGRITY ARE BEING MAINTAINED BY THE OWNER(S). IN THE EVENT THAT MAINTENANCE AND STRUCTURAL INTEGRITY ARE NOT MAINTAINED BY THE OWNER AS REQUIRED BY THE TOWNSHIP, THE OWNER HEREBY GRANTS TO THE TOWNSHIP THE RIGHT TO ENTER UPON SUCH PROPERTY AND TO PERFORM ANY AND ALL IMPROVEMENTS, REVISIONS OR MAINTENANCE AS MAY BE DETERMINED NECESSARY BY THE TOWNSHIP AND TO RECOVER THE COSTS THEREOF FROM THE PROPERTY OWNER BY ALL LAWFUL MEANS INCLUDING, BUT NOT LIMITED TO, THE IMPOSITION OF MUNICIPAL LIEN ON THE SUBJECT PROPERTY.

# CERTIFICATION OF ACCURACY

I HEREBY CERTIFY THAT THE PLAN SHOWN AND DESCRIBED HEREON, AS WELL AS ALL DRAWINGS BEARING MY SEAL, ARE TRUE AND CORRECT TO THE ACCURACY REQUIRED BY THE NEW HANOVER TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE AND WERE PREPARED BY ME OR UNDER MY DIRECTION FOR WHICH I ACCEPT FULL RESPONSIBILITY. THE PERIMETER MONUMENTS SHALL BE ACCURATELY PLACED AS REQUIRED BY THE TOWNSHIP.

MICHAEL DIPAOLO, PLS

CERTIFICATION OF OWNERSHIP COUNTY OF MONTGOMERY ON THIS, THE \_\_ DAY OF \_ UNDERSIGNED, PERSONALLY APPEARED SWORN ACCORDING TO LAW, DEPOSES AND SAYS THAT HE IS THE REPRESENTATIVE OF THE PROPERTY SHOWN ON THIS PLAN, THAT THE PLAN WAS PREPARED AT HIS DIRECTION, AND DESIRES THE SAME TO BE RECORDED AS SUCH ACCORDING TO LAW, AND THAT HE ACKNOWLEDGES THE SAME TO BE HIS ACT AND THAT ALL STREETS SHOWN AND NOT

HERETOFORE DEDICATED ARE HEREBY DEDICATED TO THE PUBLIC USE.

FDEV LLC, REPRESENTATIVE

NOTARY PUBLIC MY COMMISSION EXPIRES \_\_

**RECORDER OF DEEDS:** RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS OF MONTGOMERY COUNTY AT NORRISTOWN, PENNSYLVANIA IN THE PLAN BOOK,\_\_\_\_\_, PAGE\_\_\_\_\_, ON THE \_\_\_DAY OF\_\_\_\_\_\_, 2017.

RECORDER OF DEEDS

- 17. ALL DEVELOPMENT ACTIVITIES, SUCH AS CLEARING, GRADING, REGRADING, DRIVEWAYS, ROADS, BUILDINGS, SEPTIC SYSTEMS, RETENTION/DETENTION BASINS AND UTILITY EASEMENTS SHALL BE LIMITED TO THE NATURAL RESOURCE PROTECTION STANDARDS AS SPECIFIED IN THE NEW HANOVER TOWNSHIP ZONING ORDINANCE[CHAPTER 27] AS LAST AMENDED. THE REMAINING RESOURCES SHALL REMAIN IN ITS NATURAL CONDITION, INCLUDING THE NATURAL FOREST GROUND COVER. THIS RESTRICTION SHALL RUN WITH THE LAND AND BE BINDING ON THE PRESENT AND ALL FUTURE
- OWNERS AND/OR LESSEES. 18. THE ON LOT WELLS SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 913 OF THE SALDO.
- 19. THE STORMWATER O&M PLAN, O&M AGREEMENT AND EASEMENTS SHALL BE RECORDED PER SECTION 708 OF THE SWAMP CREEK STORMWATER MANAGEMENT PLAN.
- 20. NO PERSON SHALL MODIFY, REMOVE, FILL, LANDSCAPE, OR ALTER ANY EXISTING STORMWATER CONTROL OR BMP UNLESS IT IS PART OF AN APPROVED MAINTENANCE PROGRAM WITHOUT THE WRITTEN APPROVAL OF NEW HANOVER TOWNSHIP.
- 21. NO PERSON SHALL PLACE ANY STRUCTURE, FILL, LANDSCAPING, OR VEGETATION INTO A STORMWATER CONTROL OR BMP OR WITHIN A DRAINAGE EASEMENT THAT WOULD LIMIT OR ALTER THE FUNCTIONING OF THE STORMWATER CONTROL OR BMP WITHOUT THE WRITTEN APPROVAL OF NEW HANOVER TOWNSHIP.
- 22. EXISTING TREES ALONG LAYFIELD ROAD SHALL BE CONSIDERED STREET 23. THE AREA BETWEEN THE EXISTING AND ULTIMATE RIGHTS-OF-WAY
- HANOVER TOWNSHIP. 24. THE RIGHT-OF-WAY FOR THE PROPOSED CUL-DE-SAC IS HEREBY OFFERED FOR DEDICATION TO NEW HANOVER TOWNSHIP AND SHALL INCLUDE THE STORM DRAINAGE SYSTEM(HW1-EW1, CB1-EW3, MH1 TO HW2. MH1 TO EW2.

ALONG LAYFIELD ROAD IS HEREBY OFFERED FOR DEDICATION TO NEW

- 25. THE TREE PROTECTION STANDARDS OF SALDO SECTION 22.825.J. SHALL BE MET DURING CONSTRUCTION. 26. LOT 2 SHALL NOT BE FURTHER SUBDIVIDED, UNLESS IT MEETS ALL
- TOWNSHIP REQUIREMENTS. 27. A BLANKET 20' DRAINAGE EASEMENT IS HEREBY OFFERED PROTECTING THE NATURAL DRAINAGE FOR THE AREAS SHOWN AS WETLAND BUFFER AND EASEMENTS.
- 28. THE WOODLAND BUFFER YARD FOR EACH LOT SHALL BE PRESERVED IN ACCORDANCE WITH SECTION 27-1606.4.3 OF THE ZONING ORDINANCE. 29. PHASE 2 FINAL PLANS ARE ANTICIPATED TO BE SUBMITTED IN SPRING

WAIVER REQUEST
AT A MEETING HELD ON FEBRUARY 22, 2016 THE NEW HANOVER TOWNSHIP BOARD OF SUPERVISORS GRANTED THE FOLLOWING WAIVERS:

- 1. SECTION 22-803 TO ALLOW LOT 3 TO HAVE A LOT DEPTH TO WIDTH RATIO GREATER THAN 2.5 TO 1 (APPROXIMATELY 2.88:1) 2. SECTION 22-812.E.3 - TO NOT REQUIRE CURBING ALONG LAYFIELD
- ROAD UNLESS REQUIRED BY PENNDOT. 3. SECTION 813.6.C - TO ALLOW A FULL DEPTH PAVED STREET CARTWAY OF 20 FEET WITH 2 FOOT WIDE STRIPED SHOULDERS INSTEAD OF A 24 FOOT WIDE CARTWAY. NO ON STREET PARKING. 4. SECTION 22-813.6.C (MCMAHON IDENTIFIES AS 22-815.3) - TO NOT REQUIRE CURBING ALONG THE PROPOSED CUL-DE-SAC.
- 5. SECTION 22-822.1 TO NOT REQUIRE SIDEWALK ALONG LAYFIELD ROAD UNLESS REQUIRED BY PENNDOT. 6. SECTION 22-834 - TO NOT REQUIRE A BIKEWAY PATH ALONG THE REAR PROPERTY LINE OF THE DEVELOPMENT. 7. SECTION 22-834.2.A. - TO NOT REQUIRE THE BIKE PATH ALONG ROUTE
- BE GRADED AND THE FENCE WILL BE COMPLETED ON LOT 1. 8. SECTIONS 302.B.19 AND 410.Y - TO ALLOW A BLANKET STORMWATER EASEMENT ON EACH LOT INSTEAD OF BEING DEFINED BY BEARING AND


663 AND ALLOW A FEE IN LIEU OF THE PATH. THE BIKE PATH WILL

- AT A MEETING HELD ON JULY 28, 2016 THE NEW HANOVER TOWNSHIP ZONING HEARING BOARD APPROVED THE FOLLOWING VARIANCES:
- 1. SECTION 27-1601.F TO PERMIT INCURSIONS INTO THE 50' REQUIRED
- 2. SECTION 27-1601.I TO ALLOW STORMWATER DRAINAGE ENCROACHMENTS AND CUL-DE-SAC AND DRIVEWAY ENCROACHMENTS LOCATED WITHIN OVERLAPPING RESOURCES CONSISTENT WITH
- TESTIMONY OF THE APPLICANT. 3. SECTION 27-1606.4.3 - TO ALLOW EXISTING LANDSCAPED HOME BUFFERING RELIEF WHERE THE 3 PROPOSED LOTS TO BE SUBDIVIDED COMPLY WITH BUFFER YARD REQUIREMENTS.



# FDEV SUBDIVISION

**NEW HANOVER TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA** 



PREPARED FOR: FDEV LLC **1150 FIRST AVE STE 920** KING OF PRUSSIA, PA

PREPARED BY: 1860 WEAVERTOWN ROAD, SUITE 100 **DOUGLASSVILLE, PA 19518** PHONE: 610-689-8021 FAX: 610-689-4538

**FINAL PLAN - PHASE 1** 



**DESIGN ENGINEER** 

I, BRIAN D. BOYER, PE ON THIS DATE \_ CERTIFY THAT THE DRAINAGE PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF THE NEW HANOVER TOWNSHIP STORMWATER MANAGEMENT ORDINANCE.

Call Before You Dig!

BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA!

CALL 1-800-242-1776

NON MEMBERS MUST BE CONTACTED DIRECTLY

PA LAW REQUIRES THREE WORKING DAYS NOTICE

TO UTILITIES BEFORE YOU EXCAVATE, DRILL,

BLAST OR DEMOLISH

BRIAN D. BOYER, PE

# OWNER ACKNOWLEDGEMENT

ANY REVISIONS TO THE APPROVED POST CONSTRUCTION STORMWATER MANAGEMENT PLAN MUST BE APPROVED BY NEW HANOVER TOWNSHIP, THE CONSERVATION DISTRICT, AND/OR PADEP AND A REVISED EROSION AND SEDIMENT CONTROL PLAN MUST BE SUBMITTED TO THE CONSERVATION DISTRICT FOR A DETERMINATION OF ADEQUACY.

OWNER

TOWNSHIP ENGINEER

REVIEWED BY THE TOWNSHIP ENGINEER ON THE \_\_\_\_ DAY OF \_

TOWNSHIP ENGINEER

# **BOARD OF SUPERVISORS**

AT THE MEETING HELD ON \_ SUPERVISORS OF NEW HANOVER TOWNSHIP BY RESOLUTION\_\_\_\_\_, DULY ENACTED AND APPROVED THE SUBDIVISION PLAN OF THE PROPERTY OF FDEV LLC AS SHOWN

CHAIRMAN OF THE BOARD OF SUPERVISORS.

TOWNSHIP SECRETARY

TOWNSHIP PLANNING COMMISION

REVIEWED BY THE NEW HANOVER TOWNSHIP PLANNING COMMISSION AND RECOMMENDED FOR APPROVAL ON THE \_\_\_\_

PLANNING COMMISSION CHAIRMAN

# MONTGOMERY COUNTY PLANNING COMMISISON

PROCESSED AND REVIEWED. A REPORT HAS BEEN PREPARED BY THE MONTGOMERY COUNTY PLANNING COMMISSION IN ACCORDANCE WITH THE MUNICIPALITIES PLANNING CODE. CERTIFIED THIS DATE

MONTGOMERY COUNTY PLANNING COMMISSION

SHEET LIST 1 COVER SHEET 2 FINAL PLAN PHASE 1 3 EXISTING FEATURES PLAN 4 GRADING AND UTILITY PLAN 5 LAND DEVELOPMENT DETAIL SHEET 6 PROFILE SHEET 7 EROSION CONTROL PLAN - PROPOSED ROAD/LOT 4 8 EROSION CONTROL PLAN - LOTS 1, 2, AND 3 9 EROSION CONTROL NARRATIVE & DETAILS 10 EROSION CONTROL DETAILS 11 POST CONSTRUCTION STORMWATER MANAGEMENT/ O&M PLAN 12 AERIAL PLAN


M GENERAL PERMIT PLAN


1860 WEAVERTOWN ROAD, SUITE 100 **DOUGLASSVILLE, PA 19518** 14 - 146PHONE: 610-689-8021 FAX: 610-689-4538 2017-06-06 WJD DESIGN CHKD. BY PER MONTGOMERY COUNTY CONSERVATION DISTRICT 3/1/16, PENNDOT 12/5/16, GILMORE 12/6/16, MCMAHON 12/12/16, KMS DESIGN 12/8/16 REVIEW LETTERS 1-12-17 CS114146 PER GILMORE&ASSOCIATES, INC 3/14/16, KMS DESIGN GROUP, LLC 3/16/16, MCMAHON ASSOCIATES, INC. 2/11/16 REVIEW LETTERS. CHKD. BY SHEET NO. PER GILMORE&ASSOCIATES, INC 6/5/2015, KMS DESIGN GROUP, LLC 6/4/2015, MCMAHON ASSOCIATES, INC. WJD SCALE 1 OF 13 DATE











LOCAL CONDITIONS WILL

\_\_\_\_\_

FRONT ELEVATION VIEW

20"

TYPE D-E ENDWALL

NO SCALE

<u>PLAN VIEW</u>

24"

SIDE VIEW


TOE WALL. SEE NOTE 8

**CONCRETE END SECTIONS** SLOPE DETAIL

£----+---

GOVERN DIMENSION A D-E

L = 2.5 + 12" D-E D-E



➤ 2"x2"x36" WOODEN STAKES

AMENDED SOIL

LENGTH ABOVE

12'

12"

12"

12"

VEGETATED CHANNELS

PLACED 10' O.C.

1. THE SILT SOXX SHALL BE FILLED WITH FILTREXX GROWTH MEDIA OR OTHER APPROVED SOIL

. LIGHTLY SCARIFY SOIL IMMEDIATELY UPSLOPE OF THE BERM. PERFORM INFILTRATION TEST. PROTECT FROM

2. SEDIMENT SHALL BE REMOVED IF IT EXCEEDS ONE INCH. TRASH AND DEBRIS SHALL BE REMOVED PERIODICALLY

3. IF INFILTRATION BECOMES SIGNIFICANTLY REDUCED (GREATER THAN 72 HOURS) THE OWNER SHALL CONTACT

6. INSPECT FOR FLOW CHANNELIZATION AND RESTORE LEVEL GRADIENT IMMEDIATELY AFTER DEFICIENCIES ARE

LENGTH

88'

32'

117'

115'

INFILTRATION BERM CROSS-SECTION

2. PLACE BERM AT THE LOCATION SHOWN ON THE PLAN AVOIUDING REMOVAL OF TREES. STAKE.

AND DISPOSED IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.

SLOPE

EXISTING

EXISTING

8" EXISTING

8" EXISTING

3. PLACE AMENDED SOIL MIX 3" DEEP UPSLOPE OF THE BERM AND COVER WITH LINING MATERIAL.


MAINTENANCE NOTES

1. INSPECT AFTER EVERY RAINFALL EVENT. MONITOR DRAWDOWN TIME AFTER MAJOR STORM EVENTS.

A LICENSED PROFESSIONAL TO DETERMINE A COURSE OF ACTION TO CORRECT THE SITUATION. 4. DO NOT USE HEAVY EQUIPMENT ON THE INFILTRATION AREA AT THE UPSIDE BASE OF THE BERM.


5. MOW AND MAINTAIN THE LAWN AREAS. REMOVE INVASIVE SPECIES AS NEEDED. REMULCH AS NEEDED.

3-#13 (#4) BARS




1. SUB SOIL SHALL BE IN A LOOSE, FRIABLE CONDITION TO A DEPTH OF 20" BELOW

- FINAL GRADE. 2. SOIL AMENDMENT SPECIFICATION: COMPOST SHALL BE ADDED TO TOPSOIL AT A RATE OF 2:1 (SOIL:COMPOST). THE COMPOST SHALL HAVE A PH BETWEEN 5.0 AND 8.5, HAVE A MOISTURE CONTENT BETWEEN 30% AND 60% AND AN ORGANIC CONTENT BETWEEN 25% AND 65%. THE COMPOST SHALL HAVE 100% PASSING A 3" MESH, 90%+ PASSING A 1" MESH, 65% PASSING A 3/4" MESH, UP TO 75% PASSING THE
- 1/4" MESH. 3. SPREAD 4" OF THE COMPOST/SOIL MIX. ROTOTILL THE COMPOST AND SOIL INTO THE SUBSOIL. ADD ADDITIONAL COMPOST/SOIL MIX TO BRING TO FINAL GRADE.
- 4. PLANT SEED, RAKE, AND STABILIZE WITH MULCH. 5. MULCH SHALL BE A NATURAL SHREDDED HARDWOOD, PINE MATERIAL SHALL NOT BE




ALL CONSTRUCTION SHALL CONFORM TO PENNDOT 408, LATEST REVISION TYPICAL DRIVEWAY CROSS-SECTION



Application Activities | Section 1: Erosion & Sediment Control | 347

SEAL

# FILTREXX® RUNOFF DIVERSION



# RAIN GARDEN CROSS-SECTION

							_
	(A)	(B)	(C)	(D)	(F)	(Z)	
RG 1	453.2	10	452.70	452.2	5	4	
RG 2	436.2	10	435.7	435.2	5	4	
RG 3	461.2	10	460.70	460.2	5	4	

EACH RAIN GARDEN SHALL BE OWNED AND MAINTAINED BY THE INDIVIDUAL LOT OWNER

## RAIN GARDENS/BIORETENTION BEDS

CONSTRUCTION SEQUENCE


1. THE RAIN GARDEN SUBSOIL SHALL NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THEY SHALL BE PROTECTED FROM SEDIMENT AT ALL TIMES DURING CONSTRUCTION. THE RAIN GARDEN AREA SHALL BE PROTECTED DURING THE INSTALLATION OF THE UNIT BY USING TAPE, FENCING


- OR OTHER SUITABLE METHOD. THE EXCAVATION OF THE RAIN GARDENS SUB-GRADE CAN BE PERFORMED DURING SITE GRADING. THE RAIN GARDEN SHALL NOT BE GRADED TO WITHIN ONE FOOT OF THE FINAL BOTTOM SUB-GRADE ELEVATION UNTIL AFTER THE HOME CONSTRUCTION IS COMPLETED. THE ROOF DRAINS SHALL NOT BE
- DIRECTED TO THE RAIN GARDENS UNTIL AFTER THEY ARE CONSTRUCTED AND PLANTED (ITEM 10).

DETAILS. THE SOIL SHALL BE LIGHTLY COMPACTED WITH THE BACKHOE BUCKET. THE SOIL SHALL HAVE AN ORGANIC CONTENT OF 20-30% (COMPOST)

- 3. ANY SEDIMENT ENTERING THE RAIN GARDENS SHALL BE REMOVED WITH LIGHT EQUIPMENT. THE UNDERLYING SOIL SHALL BE SCARIFIED A MINIMUM OF SIX INCHES WITH A YORK RAKE OR ROTOTILLER.
- THE RAIN GARDENS SHALL BE BROUGHT TO GRADE PER THE DETAILS. ANY AREAS THAT ARE DAMAGED BY EROSION, HAVE WATER PONDING OR ARE COMPACTED SHALL BE REGRADED. THE BOTTOM AREA SHALL BE GRADED LEVEL.
- INSTALL THE EMERGENCY DEWATERING OUTLET PIPE AND SCREW CAP. IF UNFORESEEN CONDITIONS SUCH AS BEDROCK OR SINKHOLES ARE UNCOVERED, THE ENGINEER SHALL BE CONSULTED.
- THE 18" OF SOIL MODIFIED WITH COMPOST SHALL BE PLACED IN ACCORDANCE WITH THE DETAILS. THE SOIL SHALL BE LIGHTLY COMPACTED WITH THE BACKHOE BUCKET. THE SOIL SHALL HAVE A PH SHOULD BE BETWEEN 5.5 AND 6.5, A MAXIMUM CLAY CONTENT OF 10%, BE FREE OF TOXIC SUBSTANCES AND UNWANTED PLANT MATERIALS AND HAVE AN ORGANIC CONTENT OF APPROXIMATELY 10%. 8. THE RAIN GARDEN AREA SHALL BE PRESOAKED AND THEN THE 6" OF TOPSOIL MODIFIED WITH COMPOST SHALL BE PLACED IN ACCORDANCE WITH THE
- 9. THE PLANTS SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILS FROM MID-MARCH THROUGH MID-NOVEMBER.
- 10. THE 2" LAYER OF SHREDDED HARDWOOD MULCH (AGED A MINIMUM OF 6 MONTHS) OR COMPOST MULCH SHALL BE INSTALLED.
- 11. THE ROOF DRAIN CAN BE DIRECTED TO THE RAIN GARDEN AT THIS TIME. 12. WHEN THE DRAINAGE AREA TO EACH RAIN GARDEN IS STABILIZED (70% GRASS COVER) THE SEDIMENT CONTROL DEVICES CAN BE REMOVED. 13. WATER EACH RAIN GARDEN AT THE END OF EVERY DAY FOR TWO WEEKS.

- DO NOT ADD FERTILIZERS TO THE RAIN GARDENS. WEEDING AND PRUNING MAY BE REQUIRED WHILE THE VEGETATION IS BEING ESTABLISHED. WEEDS SHALL BE REMOVED BY HAND.
- DEAD PLANT MATERIAL SHALL BE REMOVED EVERY YEAR.
- PERENNIAL PLANTINGS SHALL BE CUT BACK AT THE END OF THE GROWING SEASON. MULCH SHALL BE RE-SPREAD WHEN IT ERODES AND BE REPLENISHED AS NECESSARY. THE AREA SHALL HAVE THE MULCH REPLACED EVERY 2 TO 3 YEARS,
- THE RAIN GARDENS MAY NEED TO BE WATERED DURING EXTENDED DROUGHT PERIODS.
- THE RAIN GARDENS SHALL BE INSPECTED AT LEAST TWO TIMES PER YEAR FOR SEDIMENT BUILDUP, EROSION, VEGETATIVE CONDITIONS, ETC.
- SEDIMENT SHALL BE REMOVED IF IT EXCEEDS ONE INCH. TRASH AND DEBRIS SHALL BE REMOVED PERIODICALLY AND DISPOSED IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.
- 9. IF INFILTRATION BECOMES SIGNIFICANTLY REDUCED (GREATER THAN 72 HOURS) OR THE VOLUME OF THE RAIN GARDEN IS REDUCED, THE TOP FEW INCHES OF SOIL SHALL BE REMOVED AND REPLACED. THE AREA SHALL BE TILLED OR AMENDED AS NECESSARY AND REPLANTED PER THE ORIGINAL
- 10. DEWATERING OF THE RAIN GARDEN SHALL OCCUR VIA THE OUTLET PIPE SHOULD STORED WATER REMAIN AFTER THE MAXIMUM 72 HOUR DETENTION





	(a)	(b)	(c)	(d)	(e)
RG-1	10'	453.2	452.70	3	EAST COAST ECP-2 BLANKET
RG-2	10'	436.2	435.7	3	EAST COAST ECP-2 BLANKET
RG-3	10'	461.2	460.70	3	EAST COAST ECP-2 BLANKET

LAND DEVELOPMENT

4/22/15

# **DIVERSION BERMS**

- INSTALL AT THE LOCATIONS SHOWN ON THE PLAN AVOIDING REMOVAL OF TREES. STAKE. 2. PLACE AMENDED SOIL MIX 3" DEEP UPSLOPE OF THE BERM AND COVER WITH LINING MATERIAL.
- 3. SEED WITH PERMANENT SEEDING.

# 4. MULCH WITH COMPOST MULCH TO PREVENT EROSION.

SEAL

- MAINTENANCE NOTES

  1. INSPECT AFTER EVERY SIGNIFICANT RAINFALL EVENT. 2. SEDIMENT SHALL BE REMOVED IF IT EXCEEDS ONE INCH. TRASH AND DEBRIS SHALL BE REMOVED PERIODICALLY AND
- DISPOSED IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS. 3. DO NOT USE HEAVY EQUIPMENT ON THE BERM.
- 4. MOW AND MAINTAIN THE LAWN AREAS. REMOVE INVASIVE SPECIES AS NEEDED. REMULCH AS NEEDED.

5. INSPECT FOR FLOW CHANNELIZATION AND RESTORE GRADIENT IMMEDIATELY AFTER DEFICIENCIES ARE OBSERVED.

POST CONSTRUCTION STORM WATER MANAGEMENT PLAN SET INCLUDES DRAWINGS PC114146, DE114146, DA114146, DA214146, AND DA314146.

CLIENT

FDEV LLC 1150 FIRST AVE STE 920 KING OF PRUSSIA, PA

19406

12" FILTREXX SILT SOXX

CAPABLE OF ESTABLISHING SEED GROWTH.

5. MULCH WITH COMPOST MULCH TO PREVENT EROSION.

BERM# | HEIGHT

4. SEED WITH PERMANENT SEEDING.

2. REFER TO SILTSOXX AT WWW.FILTREXX.COM

FILTREXX GROWTH MEDIA

DIMENSIONS FOR END SECTION								
	FOR CONCRETE PIPE							
DIAM.	Α	В	С	D	E	G	R	
18"	9"	2'-3"	3'-10"	6'-1"	3'-0"	2"	7"	
21"	9	3'-0"	3'-1"	6'-1"	3'-6"	2"	8"	
24"	<b>"</b>	3'-7"	2'-6"	6'-1"	4'-0"	3"	8"	
27"	10"	4'-0"	2'-10"	6'-1"	4'-6"	3"	9"	
30"	12"	4'-6"	1'-7"	6'-1"	5'-0"	3"	8"	
33"	13"	4'-10"	3'-10"	8'-0"	5'-6"	3"	9"	
36"	15 <b>"</b>	5'-3"	2'-9"	8'-0"	6'-0"	4"	10"	
42"	21"	5'-3"	2'-9"	8'-0"	6'-6"	4"	11"	
48"	24"	6'-0"	2'-0"	8'-0"	7'-0"	5"	12"	


# CONCRETE END SECTIONS NOTE

END VIEW

1. PROVIDE TOE WALL OF CLASS A CONCRETE.

CONSTRUCTION SEQUENCE
1. INSTALL AT THE LOCATIONS SHOWN ON THE PLAN.
2. PLACE THE SPECIFIED LINING MATERIAL.
3. SEED WITH PERMANENT SEEDING.
4. MULCH WITH COMPOST MULCH TO PREVENT EROSION.
MAINTENANCE NOTES
1. INSPECT AFTER EVERY SIGNIFICANT RAINFALL EVENT.
2. SEDIMENT SHALL BE REMOVED IF IT EXCEEDS 1/3 THE DEPTH OF THE CHANNEL. TRASH AND DEBRIS SHALL BE REMOVED
PERIODICALLY AND DISPOSED IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.
3. DO NOT USE HEAVY EQUIPMENT ON THE CHANNEL.
4. MOW AND MAINTAIN THE LAWN AREAS. REMOVE INVASIVE SPECIES AS NEEDED. REMULCH AS NEEDED.
5. INSPECT FOR FLOW CHANNELIZATION AND RESTORE GRADIENT IMMEDIATELY AFTER DEFICIENCIES ARE OBSERVED.

4.	FINAL PLAN — PHASE 1	2017-06-06	MND	BDB
3.	PER MONTGOMERY COUNTY CONSERVATION DISTRICT 3/1/16, PENNDOT 12/5/16, GILMORE 12/6/16, MCMAHON 12/12/16, KMS DESIGN 12/8/16 REVIEW LETTERS	1-12-17	JCE	BDB
	PER GILMORE&ASSOCIATES, INC 3/14/16, KMS DESIGN GROUP, LLC 3/16/16, MCMAHON ASSOCIATES, INC. 2/11/16 REVIEW LETTERS.	10-25-16	WJD	BDB
1.	PER GILMORE&ASSOCIATES, INC 6/5/2015, KMS DESIGN GROUP, LLC 6/4/2015, MCMAHON ASSOCIATES, INC. 6/5/2015, AND MONTGOMERY COUNTY PLANNING COMMISSION 6/30/2015 REVIEW LETTERS.	10-21-15	MJD	BDB
NO.	REVISION	DATE	BY	APP.



1860 WEAVERTOW	PROJECT NO.		
DOUGLASSVII PHONE: 61 FAX: 610	14-146		
		DWG. NO.	
DESIGN	CHKD. BY		
BDB		DE114146	
DRAWN BY	CHKD. BY		
WJD		SHEET NO.	

5 OF 13


SCALE


SUBJECT


FDEV SUBDIVISION

NEW HANOVER TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

& POST CONSTRUCTION STORMWATER MANAGEMENT DETAIL SHEET







Soil Name	CrB - Croton Silt Loam,	LhB – Lehigh Silt Loam	LhC - Lehigh Silt
	3 to 8% slopes	3 to 8% Slopes	Loam, 8 to 15% slopes
Depth to Seasonal Water Table (in)	0 to 6	6 to 36	6 to 36
Depth to Bedrock (in)	40 to 60	40 to 60	40 to 60
pН	Variable Use Soil tests to determine	Variable Use Soil tests to determine	Variable Use Soil tests to determine
Suitability for Winter Grading	Poor (Wetness)	Fair (Depth to Saturated Zone)	Fair (Depth to Saturated Zone)
Susceptibility to Frost Action	High (Wetness)	High (Depth to Saturated Zone)	High (Depth to Saturated Zone)
Topsoil Suitability	Poor (Wetness)	Poor (Rock Fragments)	Poor (Rock Fragments)
Road Fill Suitability	Poor (Wetness)	Fair (Depth to Saturated Zone)	Fair (Depth to Saturated Zone)
Highway Location	Very Limited (Ponding, Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone, Frost Action)	Very Limited (Depth to Saturated Zone, Frost Action)
Shallow Excavations	Very Limited (Ponding, Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone)
Embankment Suitability for Detention Basins	Very Limited (Ponding, Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone)
Landscaping and Lawn Suitability	Very Limited (Depth to Saturated Zone, Ponding)	Somewhat Limited (Depth to Saturated Zone)	Somewhat Limited (Depth to Saturated Zone)
On-site Sewage Disposal Suitability	Very limited (Depth to Saturated Zone)	Very Limited (Slow Percolation)	Very Limited (Slow percolation)
Home Site Suitability with Basement	Very Limited (Ponding, Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone)	Very Limited (Depth to Saturated Zone)
Corrosion of Concrete	Moderate	Low	Low
Mechanical Site Preparation (Deep)	Well Suited	Well Suited	Well Suited
Hydrologic Soil Group	D	C/D	C/D

A SITE WITH AN APPROVED EROSION CONTROL PLAN.

Soil Characteristics

PH - THE TOPSOIL SHALL BE TESTED PRIOR TO APPLYING THE SEED AND MULCH. LIME SHALL BE ADDED TO THE SOIL ∜NTIL IT REACHES A PH OF 7 TO 7.5

WINTER GRADING - THE SOILS SHALL BE STABILIZED WITH MULCH UNTIL IT IS APPROPRIATE TO APPLY THE SEED. FROST ACTION - SOILS CONTAINING FROST SHALL NOT BE UTILIZED AS STRUCTURAL BACKFILL.

TOPSOIL - THE TOPSOIL SHALL HAVE LIME APPLIED AS NECESSARY TO HAVE A PH OF 7 TO 7.5. COMPOST SHALL BE MIXED WITH THE TOPSOIL PER THE AMENDED SOIL SPECIFICATION TO INCREASE ITS ORGANIC CONTENT AND WATER HOLDING CAPACITY. ANY TOPSOIL THAT NEEDS TO BE IMPORTED SHALL BE FROM A SITE WITH AN APPROVED EROSION CONTROL PLAN. ROAD FILL - SUITABLE MATERIAL SHALL BE FOUND ONSITE OR IMPORTED FROM A SITE WITH AN APPROVED EROSION CONTROL PLAN.

HIGHWAY LOCATION - LIMITATIONS INCLUDE WETNESS AND LOW STRENGTH. IF BEDROCK IS ENCOUNTERED IT SHALL BE REMOVED TO AN APPROPRIATE DEPTH AND THE STONE BASE FOR THE ROAD SHALL BE INSTALLED. ROADS SHALL NOT BE CONSTRUCTED WHEN THE TEMPERATURE IS BELOW FREEZING UNLESS THE FROZEN SOILS ARE REMOVED PIPELINE CONSTRUCTION - LIMITATIONS MAY INCLUDE HIGH WATER TABLE. UTILITY TRENCHES SHALL BE PUMPED TO KEEP

THE WORKING AREA DRY. ALL PUMPED WATER SHALL BE DISCHARGED TO A SEDIMENT FILTERING DEVISE. DETENTION BASIN EMBANKMENTS - THE LIMITATION IS THE LOW STRENGTH. ANY SOIL THAT IS IMPORTED SHALL COME FROM

TERRACES AND WATERWAYS -APPROPRIATE STABILIZATION MATERIALS SHALL BE USED AS SPECIFIED IN THE PLANS. LANDSCAPING AND LAWN - LIMITATIONS INCLUDE POOR AND LIMITED AMOUNTS OF TOPSOIL AND WET SOILS. SOIL AMENDMENT WITH COMPOST AND SAND SHALL BE USED TO PROVIDE ADEQUATE PLANTING SOIL. ANY SOIL THAT IS IMPORTED SHALL COME FROM A SITE WITH AN APPROVED EROSION CONTROL PLAN. SLOPED AREAS SHALL BE MULCHED AND

HAVE THE APPROPRIATE NETTING INSTALLED WHERE NECESSARY TO PREVENT EROSION. 102.4(B)(5)(III) - THE CHARACTERISTICS OF THE EARTH DISTURBANCE ACTIVITY, INCLUDING THE PAST, PRESENT AND PROPOSED LAND USES AND THE PROPOSED ALTERATION TO THE PROJECT SITE.

THE PRESENT LAND USE IS SINGLE FAMILY RESIDENTIAL. THE PAST LAND USE IS SINGLE FAMILY RESIDENTIAL. THE PROPOSED LAND USE IS SINGLE FAMILY RESIDENTIAL. THE LAND WILL BE REGRADED TO CONSTRUCT THE IMPROVEMENTS.

. 102.4(B)(5)(IV) - THE AMOUNT OF RUNOFF FROM THE PROJECT AREA AND ITS UPSTREAM AREA. THE MAXIMUM DURING CONSTRUCTION DRAINAGE AREAS TOTAL 4.55 ACRES. THE ENTIRE DRAINAGE AREA IS CONTROLLED BY SILTSOXX DURING CONSTRUCTION. IN POST-CONSTRUCTION RAIN GARDENS AND INFILTRATION BERMS CONTROL THE

RUNOFF, WHILE THE REMAINDER IS CONSIDERED BYPASS. OFFSITE RUNOFF DOES NOT ENTER THE DEVELOPMENT AREA.

ACCORDING TO THE TOWNSHIP'S ORDINANCE REQUIREMENTS. VII. 102.4(B)(5)(V) - THE LOCATION OF WATERS OF THE COMMONWEALTH WHICH MAY RECEIVE RUNOFF WITHIN OR FROM THE PROJECT SITE AND THEIR CLASSIFICATION PURSUANT TO CHAPTER 93 OF THIS TITLE.

PEAK FLOWS ARE REDUCED FROM POSTDEVELOPED CONDITIONS TO PREDEVELOPED CONDITIONS FOR ALL STORMS

THE SITE IS TRIBUTARY TO THE SWAMP CREEK, PA CODE CHAPTER 93 CLASSIFICATION OF TSF.

VIII.102.4(B)(5)(VI) - A WRITTEN DEPICTION OF THE LOCATION AND TYPE OF PERIMETER AND ON SITE BMP'S USED BEFORE, DURING, AND AFTER THE EARTH DISTURBANCE ACTIVITY.

THE LOCATION OF THE PROPOSED TEMPORARY AND PERMANENT BMP'S AND THEIR CONSTRUCTION DETAILS ARE SHOWN ON THE EROSION CONTROL PLANS AND DETAIL SHEET. THE WORKSHEETS AND CALCULATIONS ARE PROVIDED IN APPENDIX C.

1. ONLY LIMITED DISTURBANCE WILL BE PERMITTED TO PROVIDE ACCESS TO (CONSTRUCT SEDIMENT TRAPS, DIVERSION

E. EROSION AND SEDIMENTATION CONTROLS MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE WITHIN THE TRIBUTARY AREAS OF THOSE CONTROLS.

B. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE CONTROLS MUST BE STABILIZED IMMEDIATELY. 4. VEHICLES AND EQUIPMENT MUST USE THE DESIGNATED DRIVEWAY ENTRANCES ONTO PARK AVENUE. AT NO TIME SHALL

CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE OF THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS

5. AT THE END OF EACH WORKING DAY, ANY SEDIMENT TRACKED OR CONVEYED ONTO A PUBLIC ROADWAY OR SIDEWALK WILL BE REMOVED AND RE-DEPOSITED ONTO THE CONSTRUCTION SITE. REMOVAL CAN BE COMPLETED THROUGH USE OF MECHANICAL OR HAND TOOLS, BUT MUST NEVER BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR

SEDIMENT REMOVED FROM E&SPC CONTROLS & FACILITIES SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF WETLANDS OR DRAINAGE SWALES AND IMMEDIATELY STABILIZED OR PLACED ON TOPSOIL STOCKPILES. . ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A DIRT BAG FILTRATION DEVICE OR EQUIVALENT SEDIMENT REMOVAL FACILITY, OVER NON-DISTURBED VEGETATED AREAS. DISCHARGE POINTS SHOULD BE ESTABLISHED TO PROVIDE FOR

MAXIMUM DISTANCE TO ACTIVE WATERWAYS. 8. AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS, AND OTHER OBJECTIONABLE MATERIAL. 9. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED

PROBLEMS. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 9 INCHES IN THICKNESS. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES. .0. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS. FROZEN MATERIALS OR SOFT.

MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILL L. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED METHOD.

2. ALL EXCAVATION FOR UTILITY LINE INSTALLATION SHALL BE LIMITED TO THE AMOUNT THAT CAN BE EXCAVATED, INSTALLED, BACKFILLED AND STABILIZED WITHIN ONE WORKING DAY. ALL EXCAVATED MATERIAL SHALL BE DEPOSITED ON THE UPSLOPE SIDE OF THE TRENCH. 3. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR

SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENT POLLUTION AND NOTIFY THE MONTGOMERY COUNTY CONSERVATION DISTRICT AND/OR REGIONAL DEP OFFICE. STOCKPILES OF WOOD CHIPS, HAY BALES, CRUSHED STONE AND OTHER MULCHES SHALL BE HELD IN READINESS TO DEAL IMMEDIATELY WITH EMERGENCY PROBLEMS OF EROSION.

4. THE CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF THE APPENDIX 64, EROSION CONTROL RULES AND REGULATIONS, TITLE 25, PART 1, DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION OF NATURAL RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL.

15. A COPY OF THIS EROSION AND SEDIMENTATION CONTROL REPORT AND PLANS MUST BE POSTED AT THE CONSTRUCTION SITE 16. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/ OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR

# TEMPORARY CONTROL MEASURES AND FACILITIES FOR USE DURING EARTHMOVING

. SILT SOXX AND/OR SILT FENCE SHALL BE INSTALLED AT LOCATIONS NOTED ON THE PLAN PRIOR TO ANY DISTURBANCE OF THE EXISTING GROUND COVER, DURING THE CONSTRUCTION PHASE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OR REPLACING SILT SOXX AND SILT FENCE AFTER EACH RAINFALL EVENT TO INSURE CONTINUED OPERATION. SEDIMENTATION DETENTION BASINS/TRAPS SHALL BE CONSTRUCTED AND MUST BE STABILIZED PRIOR TO ANY EARTHMOVING. SWALES SHOULD BE CONSTRUCTED AND STABILIZED AT THIS TIME, UNLESS OTHERWISE NOTED.

STONE BASE COURSES FOR ROADS AND DRIVEWAYS SHALL BE PLACED AS SOON AS PRACTICAL. 4. STOCKPILES OF MULCHES, SUCH AS WOOD CHIPS, CRUSHED STONE, STRAW AND JUTE MESH SHALL BE KEPT ONSITE AND BE AVAILABLE TO DEAL WITH EROSIVE CONDITIONS AS THEY ARISE. . ALL CUT AND FILL SLOPE AREAS WHOSE SURFACES ARE SUBJECT TO EROSIVE ACTION SHALL BE PROTECTED WITH ONE OF THE

MULCHES IN ITEM 4 ABOVE. 5. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES HAVE CEASED IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING THE NON-GERMINATING PERIODS, MULCH OR PROTECTIVE BLANKETING MUST BE APPLIED AT THE RECOMMENDED RATE. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE RE-DISTURBED WITHIN ONE YEAR MAY BE SEEDED AND MULCHED WITH A QUICK GROWING TEMPORARY SEEDING MIXTURE AND

MULCH. DISTURBED AREAS WHICH ARE EITHER AT FINISHED GRADE OR WILL NOT BE RE-DISTURBED WITHIN ONE YEAR MUST BE SEEDED AND MULCHED WITH A PERMANENT SEED MIXTURE AND MULCH. ALL UN-STABILIZED, DISTURBED AREAS ARE TO BE PREPARED AND SEEDED FOLLOWING THE FINAL GRADING. ALL TEMPORARY CONTROLS ARE TO REMAIN IN PLACE DURING THE ENTIRE CONSTRUCTION PHASE UNTIL THE SOIL HAS BEEN

# STABILIZED, UNLESS OTHERWISE NOTED.

# STABILIZATION NOTES

EEDING SPECIFICATIONS

. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION SHOWN ON THE PLAN. IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION. EACH STOCKPILE SHALL BE PROTECTED BY A COMPOST FILTER SOCK. STOCKPILE HEIGHTS MUST NOT EXCEED 35' STOCKPILE SLOPES MUST BE 2:1 OR FLATTER.

AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES, 6 TO 12 INCHES ON COMPACTED SOILS, PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM OF 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL.

. UPON TEMPORARY CESSATION OR COMPLETION OF AN EARTH DISTURBANCE ACTIVITY OR ANY STAGE OR PHASE OF AN ACTIVITY WHERE A CESSATION OF FARTH DISTURBANCE ACTIVITIES EXCEED 4 DAYS. THE OPERATOR SHALL IMMEDIATELY SEED AND MULCH OR OTHERWISE PROTECT THE SITE FROM ACCELERATED EROSION AND SEDIMENTATION PENDING FURTHER EARTH DISTURBANCE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE RE-DISTURBED WITHIN 1 YEAR MAY BE STABILIZED IN ACCORDANCE WITH TEMPORARY SEEDING SPECIFICATIONS. DISTURBED AREAS, WHICH ARE FITHER AT

FINISHED GRADE OR WILL NOT BE RE-DISTURBED WITHIN 1 YEAR, MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT

4. DIVERSION CHANNELS, SEDIMENTATION BASINS, SEDIMENT TRAPS, AND STOCKPILES MUST BE STABILIZED IMMEDIATELY. 5. HAY OR STRAW MULCH MUST BE APPLIED AT RATES OF AT LEAST 3.0 TONS PER ACRE.

6. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN

COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR OTHERWISE SHOWN ON THE PLAN DRAWINGS, SHALL BE BLANKETED ACCORDING TO THE PLAN. 7. UNTIL THE SITE HAS ACHIEVED FINAL STABILIZATION THE OWNER AND/OR CONTRACTOR SHALL PROPERLY IMPLEMENT, OPERATE AND MAINTAIN ALL THE BEST MANAGEMENT PRACTICES. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROL AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL

8. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER

MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR

9. MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES GREATER THAN

MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING,

# PERMANENT CONTROL MEASURES AND FACILITIES FOR LONG TERM PROTECTION

THE FOLLOWING ACTIVITIES SHALL BE UNDERTAKEN TO ACHIEVE PERMANENT STABILIZATION OF ALL EXPOSED AND DISTURBED SOIL AREAS AS REQUIRED OR DIRECTED.

PERMANENT VEGETATIVE SURFACE STABILIZATION SITE PREPARATION - INCORPORATE LIME AND FERTILIZER (RATE BASED UPON SOIL TESTING) AS DEEPLY INTO THE SOIL AS POSSIBLE. IF SOIL TESTS ARE NOT AVAILABLE, APPLY FOUR TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 10-20-20

SEEDING - ALL DISTURBED AREAS SHALL BE PREPARED AND SEEDED WITH THE SPECIES THE NOTED SEEDING RATE FOLLOWING THE FINAL GRADING.

## TEMPORARY AND PERMANENT STABILIZATION SPECIFICATIONS TEMPORARY SEEDING

MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED.

SPECIES: ANNUAL RYEGRASS % PURE LIVE SEED: APPLICATION RATE 40 LBS. PER ACRE FERTILIZER TYPE: 10-20-20 FERTILIZER APPLICATION RATE: 150 LBS. PER ACRE

AGRICULTURAL GRADE LIMESTONE A AT 1 TON PER ACRE LIMING RATE: MULCH TYPE: HAY OR STRAW MULCHING RATE: 3 TONS PER ACRE

# PERMANENT SEEDING

ANCHOR MATERIAL:

TALL FESCUE (39%), FINE FESCUE (38%), ALSIKE CLOVE (20%), REDTOP (3%) SPECIES: % PURF LIVE SEED:

20, 10, 20 AND 12 LBS. PER ACRE, RESPECTIVELY APPLICATION RATE FERTILIZER TYPE: AS PER SOIL TESTING RESULTS FERTILIZER APPLICATION RATE: AS PER SOIL TESTING RESULTS LIMING RATE: AGRICULTURAL GRADE LIMESTONE A AT 4 TON PER ACRE MULCH TYPE HAY OR STRAW MULCHING RATE: 3 TONS PER ACRE

ANCHORING METHOD CLEAT WITH DEEP CLEATS SEEDING SEASON DATES: MARCH THROUGH JUNE, SEPTEMBER, OCTOBER

## PERMANENT STEEP SLOPE SEEDING

TALL FESCUE, ALSIKE % PURE LIVE SEED:

20 AND 10 LBS, PER ACRE, RESPECTIVELY APPLICATION RATE: FERTILIZER TYPE: AS PER SOIL TESTING RESULTS FERTILIZER APPLICATION RATE: AS PER SOIL TESTING RESULTS AGRICULTURAL GRADE LIMESTONE A AT 4 TON PER ACRE LIMING RATE: MUI CH TYPE: HAY OR STRAW

MULCHING RATE: 3 TONS PER ACRE ANCHOR MATERIAL: EAST COAST BLANKETS ECSC-2 OR EQUAL ANCHORING METHOD: STAPLES MARCH THROUGH JUNE, SEPTEMBER, OCTOBER SEEDING SEASON DATES:

A NURSE CROP OF OATS SHALL BE USED WITH THE PERMANENT SEEDING AT A RATE OF 45 LBS PER ACRE.

1. ALL CHANNELS MUST BE KEPT FREE OF OBSTRUCTIONS SUCH AS FILL GROUND. FALLEN I FAVES & WOODY DEBRIS ACCUMULATED SEDIMENT, AND CONSTRUCTION MATERIALS/WASTES. CHANNELS SHOULD BE KEPT MOWED AND/OR FREE OF ALL WEEDY, BRUSHY OR WOODY GROWTH, ANY UNDERGROUND UTILITIES RUNNING ACROSS/ THROUGH THE CHANNEL(S) SHALL BE IMMEDIATELY BACKFILLED AND THE CHANNEL(S) REPAIRED AND STABILIZED PER THE CHANNEL CROSS-SECTION

2. VFGFTATFD CHANNELS SHALL BE CONSTRUCTED FREE OF ROCKS, TREE ROOTS, STUMPS OR OTHER PROJECTIONS THAT WILL IMPEDE NORMAL CHANNEL FLOW AND/OR PREVENT GOOD LINING TO SOIL CONTACT. THE CHANNEL SHALL BE INITIALLY OVER-EXCAVATED TO ALLOW FOR THE PLACEMENT OF TOPSOIL.

## UTILITY LINE TRENCH EXCAVATION

1. LIMIT ADVANCE CLEARING AND GRUBBING OPERATIONS TO A DISTANCE EQUAL TO TWO TIMES THE LENGTH OF PIPE INSTALLATION THAT CAN BE COMPLETED IN ONE DAY. 2. WORK CREWS AND EQUIPMENT FOR TRENCHING, PLACEMENT OF PIPE, PLUG CONSTRUCTION AND BACKFILLING WILL BE SELF

3. LIMIT THE DAILY TRENCH EXCAVATION TO THE LENGTH OF PIPE PLACEMENT, PLUG INSTALLATION AND BACKFILLING THAT CAN BE 4. WATER WHICH ACCUMULATES IN THE OPEN TRENCH WILL BE COMPLETELY REMOVED BY PUMPING BEFORE PIPE PLACEMENT AND/OR BACKELLING BEGINS. THE SEEPAGE MUST BE PLIMPED TO A FACILITY FOR REMOVAL OF SEDIMENT. THIS FACILITY MUST BELOCATED OUTSIDE OF THE CHANNEL TE FYCAVATION TRENCHES ARE UNDERNEATH OR ADJOINING SMALL STREAMS.

CONTAINED AND SEPARATE FROM CLEARING AND GRUBBING AND SITE RESTORATION AND STABILIZATION OPERATIONS.

5. ON THE DAY FOLLOWING PIPE PLACEMENT AND TRENCH BACKFILLING, THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS AND MEASURES/FACILITIES SHALL BE INSTALLED. SEEDING AND MULCHING OF ALL DISTURBED AREAS SHALL BE

6. IN CERTAIN CASES TRENCHES CANNOT BE BACKFILLED UNTIL THE PIPE IS HYDROSTATICALLY TESTED. OR ANCHORS AND OTHER PERMANENT FEATURES ARE INSTALLED. IN THESE CASES, ALL OF THE REQUIREMENTS UNDER ITEMS 1 THROUGH 5 WILL REMAIN IN EFFECT WITH THE FOLLOWING EXCEPTIONS:

a. DAILY BACKFILLING OF THE TRENCH MAY BE DELAYED FOR SIX DAYS. ALL PRESSURE TESTING AND THE COMPLETE BACKFILLING OF THE OPEN TRENCH MUST BE COMPLETED BY THE SEVENTH WORKING DAY. h IE DAILY BACKEILLING IS DELAYED. THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS. APPROPRIATE

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES/FACILITIES WILL BE INSTALLED AND THE AREA SEEDED AND MULCHED WITHIN THE NEXT TWO CALENDAR DAYS.

# RAIN GARDEN INSTALLATION PROCEDURES

1. THE RAIN GARDEN SHALL BE EXCAVATED TO THE PRESCRIBED DEPTH SHOWN ON THE PLAN DETAILS. THE BOTTOM OF THE EXCAVATION SHALL BE LEVEL. USE THE LIGHTEST EQUIPMENT POSSIBLE. THE BOTTOM OF THE EXCAVATION SHALL NOT BE COMPACTED AND SHALL BE FREE FROM ROCKS AND DEBRIS. A LICENSED PROFESSIONAL SHOULD PROVIDE OVERSIGHT DURING

2. ANY SEDIMENT ENTERING THE RAINGARDENS SHALL BE REMOVED WITH LIGHT EQUIPMENT. THE UNDERLYING SOIL SHALL BE SCARIFIFD A MINIMUM OF TWELVE (12) INCHES WITH A YORK RAKE, SUBSOILER OR OTHER SUITABLE EQUIPMENT. A LICENSED PROFESSIONAL SHOULD PROVIDE OVERSIGHT DURING THE SCARIFYING OF THE SUBGRADE 3. THE BOTTOM OF THE RAIN GARDEN SHALL HAVE THE AMENDED SOIL INSTALLED.

4. STABILIZE THE DISTURBED AREAS WITH PERMANENT SEEDING AND PLANTINGS, AND MULCH IMMEDIATELY UPON COMPLETION.

IX. 102.4(B)(5)(VII) - A SEQUENCE OF BMP INSTALLATION AND REMOVAL IN RELATION TO THE SCHEDULING OF EARTH DISTURBANCE ACTIVITIES, PRIOR TO, DURING AND AFTER EARTH DISTURBANCE ACTIVITIES.

APPROXIMATE START DATE FOR CONSTRUCTION - MARCH 2018

APPROXIMATE END DATE FOR CONSTRUCTION - DECEMBER 2019

1. ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS, BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED, AND DATED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE MONTGOMERY COUNTY CONSERVATION DISTRICT SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE MONTGOMERY COUNTY CONSERVATION DISTRICT MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR

2. EACH STAGE SHALL BE COMPLETED IN COMPLIANCE WITH CHAPTER 102 REGULATIONS BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE. 3. AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE

4. AT LEAST 3 DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND

BMP'S, AND A REPRESENTATIVE OF THE MONTGOMERY COUNTY CONSERVATION DISTRICT TO AN ON-SITE PRE-CONSTRUCTION

5. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT.

6. CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF

OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN. 7. THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET SEQ., 271.1 E. SEQ. AND 287.1 ET SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED,

CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING, AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE

DUMPED, OR DISCHARGED AT THE SITE. 8. BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE OPERATOR MUST ASSURE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE LOCAL COUNTY CONSERVATION DISTRICT OR THE DEPARTMENT OF ENVIRONMENTAL PROTECTION, AND WHICH IS FULLY IMPLEMENTED AND MAINTAINED ACCORDING TO CHAPTER 102 REGULATIONS PRIOR TO BEING ACTIVATED. THE OPERATOR SHALL ALSO NOTIFY THE MONTGOMERY COUNTY CONSERVATION DISTRICT IN WRITING OF ALL RECEIVING SPOIL AND BORROW AREAS WHEN THEY HAVE BEEN IDENTIFIED. 9. THE OPERATOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT TO THE SITE IS CLEAN FILL. FORM FP-001 MUST

## THE GENERAL SEQUENCE OF CONSTRUCTION IS AS FOLLOWS. IF ANY MODIFICATIONS ARE NECESSARY OR DESIRED BY THE CONTRACTOR, THEY MUST BE APPROVED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT PRIOR TO IMPLEMENTING THE CHANGES.

BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED

SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING.

# A. SITE IMPROVEMENTS-LOT 4

1. THE LIMIT OF DISTURBANCE (LOD) SHALL BE MARKED WITH SURVEY STAKES, POSTS AND ROPE, CONSTRUCTION FENCE OR SOME OTHER ACCEPTABLE MATERIAL PRIOR TO DISTURBANCE ACTIVITIES. 2. THE CONSTRUCTION ENTRANCE SHALL BE ESTABLISHED WHERE SHOWN ON THE PLAN, INCLUDING THE TIRE WASH AREA. THIS SHALL BE THE ONLY ENTRANCE AND EXIT FROM THE SITE FOR THE CONSTRUCTION VEHICLES.

3. THE SILT FENCE # 1 AND #2 SHALL BE INSTALLED WHERE SHOWN ON THE PLAN. SILT FENCE MUST BE PROPERLY FUNCTIONING BEFORE THE CONSTRUCTION OF TRIBUTARY IMPROVEMENTS.

LIPON THE INSTALLATION OR STABILIZATION OF ALL PERIMETER SEDIMENT CONTROL RMP'S AND AT LEAST 3 DAYS PRIOR TO PROCEEDING WITH THE BULK EARTH DISTURBANCE ACTIVITIES, THE PERMITTEE OR CO-PERMITTEE SHALL PROVIDE

# NOTIFICATION TO THE MONTGOMERY COUNTY CONSERVATION DISTRICT.

4. THE CONTRACTOR SHALL ENSURE THAT THE RUNOFF FROM ALL POSSIBLE EARTH DISTURBANCE ACTIVITIES SHALL CONSTANTLY BE DIRECTED INTO EROSION CONTROLS WHERE APPLICABLE 5. STRIP THE TOPSOIL FROM CONSTRUCTION AREA AND PLACE WHERE SHOWN ON THE PLAN. ANY EXCESS TOPSOIL MAY BE HAULED

OFFSITE TO A FACILITY WITH AN APPROVED EROSION CONTROL PLAN. ANY REQUIRED FILL IMPORTED TO THE SITE SHALL MEET THE CLEAN FILL REQUIREMENTS AND THE SITE SHALL HAVE AN APPROVED EROSION CONTROL PLAN. 6. CONSTRUCT THE NEW SEWAGE ABSORPTION AREA, CONNECT TO EXISTING HOUSE.

7. STABILIZE DISTURBED AREAS WITH TEMPORARY SEEDING AND MULCH IN LAWN AREAS. NO MORE THAN 15,000 SQUARE FEET OF DISTURBED AREA SHALL REACH FINAL GRADE BEFORE INITIATING STABILIZATION OPERATIONS. 8. REMOVE THE EXISTING SEWER LATERAL RUN TO THE EXISTING SEWAGE ABSORPTION AREA. FOLLOW **UTILITY LINE TRENCH** 

a. LIMIT ADVANCE CLEARING AND GRUBBING OPERATIONS TO A DISTANCE EQUAL TO TWO TIMES THE LENGTH OF PIPE REMOVAL THAT CAN BE COMPLETED IN ONE DAY, ALL EFFORTS TO PRESERVE EXISTING TREES SHALL BE MADE. b. WORK CREWS AND EQUIPMENT FOR TRENCHING, REMOVAL OF PIPE, AND BACKFILLING WILL BE SELF-CONTAINED AND SEPARATE FROM CLEARING AND GRUBBING AND SITE RESTORATION AND STABILIZATION OPERATIONS.

C. LIMIT THE DAILY TRENCH EXCAVATION TO THE LENGTH OF PIPE REMOVAL AND BACKFILLING THAT CAN BE COMPLETED d. WATER WHICH ACCUMULATES IN THE OPEN TRENCH WILL BE COMPLETELY REMOVED BY PUMPING BEFORE BACKFILLING

REGINS. THE SEEPAGE MUST BE PLIMPED TO A FACILITY FOR REMOVAL OF SEDIMENT. THIS FACILITY MUST BE LOCATED. OUTSIDE OF THE CHANNEL IF EXCAVATION TRENCHES ARE UNDERNEATH OR ADJOINING SMALL STREAMS e. ON THE DAY FOLLOWING TRENCH BACKFILLING, THE DISTURBED AREA WILL BE GRADED TO EXISTING CONTOURS.

SEEDING AND MULCHING OF ALL DISTURBED AREAS SHALL BE COMPLETED AT THE END OF EACH WEEK. f. IF DAILY BACKFILLING IS DELAYED, THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS, APPROPRIATE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES/FACILITIES WILL BE INSTALLED AND THE AREA SEEDED AND MULCHED WITHIN THE NEXT TWO CALENDAR DAYS.

WHEN ALL OF THE DISTURBANCES ON LOT 4 ARE COMPLETELY STABILIZED (A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER), ALL TEMPORARY BMP'S SHOULD BE REMOVED FROM THE SITE (INCLUDING ALL SILT FENCE) AND ANY DISTURBANCE CREATED WHEN REMOVING THEM SHALL IMMEDIATELY BE PERMANENTLY SEEDED AND MULCHED. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING GERMINATING SEASON.

## B. SITE IMPROVEMENTS-PROPOSED ROAD

**EXCAVATION/REMOVAL PROCEDURES:** 

9. THE LIMIT OF DISTURBANCE (LOD) SHALL BE MARKED WITH SURVEY STAKES, POSTS AND ROPE, CONSTRUCTION FENCE OR SOME OTHER ACCEPTABLE MATERIAL PRIOR TO DISTURBANCE ACTIVITIES. CONSTRUCTION FENCE SHALL BE USED IN WOODED AREAS TO ACT AS TREE PROTECTION FENCE AND TO DELINEATE THE EXTENT OF EARTH MOVING AREAS. 10. A TEMPORARY CONSTRUCTION ENTRANCE SHALL BE ESTABLISHED UPSLOPE OF THE PROPOSED ROAD LOCATION. THIS SHALL BE

THE ONLY ENTRANCE AND EXIT FROM THE SITE FOR CONSTRUCTION VEHICLES FOR THE CONSTRUCTION OF THE UTILITY CROSSINGS ASSOCIATED WITH CHAPTER 105 GENERAL PERMITS (GP). 11. INSTALL SILT SOCKS #1, #2 AND #3 WHERE SHOWN ON THE PLAN. SILT SOCK MUST BE PROPERLY FUNCTIONING BEFORE THE CONSTRUCTION OF TRIBUTARY IMPROVEMENTS.

### UPON THE INSTALLATION OR STABILIZATION OF ALL PERIMETER SEDIMENT CONTROL BMP'S AND AT LEAST 3 DAYS PRIOR TO PROCEEDING WITH THE BULK EARTH DISTURBANCE ACTIVITIES, THE PERMITTEE OR CO-PERMITTEE SHALL PROVIDE NOTIFICATION TO THE MONTGOMERY COUNTY CONSERVATION DISTRICT

12. INSTALL THE CONCRETE WASHOUT. 13. CLEAR AND GRUB AREAS OF GP STORM SEWERS AND SWALE 1 & 2.

14. INSTALL STORM SEWER PIPES, STRUCTURES, AND RIPRAP ASSOCIATED WITH PIPE RUN EW2-MH1-HW2 AND THE CONNECTION TO THE EXISTING PIPE CROSSING LAYFIELD ROAD. 15. INSTALL AND STABILIZE SWALE 1.

16. INSTALL STORM SEWER PIPES, STRUCTURES, AND RIPRAP ASSOCIATED WITH PIPE RUN EW1-HW1. 17. INSTALL AND STABILIZE SWALE 2. 18. CLEAR AND GRUB AREAS FOR PROPOSED ROAD CONSTRUCTION, 5. STRIP THE TOPSOIL FROM CONSTRUCTION AREA AND PLACE WHERE SHOWN ON THE PLAN. ANY EXCESS TOPSOIL MAY BE HAULED OFFSITE TO A FACILITY WITH AN APPROVED EROSION

CONTROL PLAN. ANY REQUIRED FILL IMPORTED TO THE SITE SHALL MEET THE CLEAN FILL REQUIREMENTS AND THE SITE SHALL HAVE AN APPROVED EROSION CONTROL PLAN. 19. ROUGH GRADE PROPOSED ROAD AND FIRST 25 FEET OF PROPOSED DRIVEWAYS ON LOTS 1 & 3 AND THE FIRST 215 FEET ON LOT STABILIZE THESE AREAS.

20. CONSTRUCT RAIN GARDEN 1 ACCORDING TO THE **RAIN GARDEN INSTALLATION PROCEDURES.** THE AREA OF THE RAIN GARDEN SHALL BE NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THE AREA SHALL BE PROTECTED BY USING TAPE, FENCING OR OTHER SUITABLE METHOD. 21. INSTALL STORM SEWER PIPES, STRUCTURES, AND RIPRAP ASSOCIATED WITH PIPE RUN EW3-INLET 1.

22. FINAL GRADE ROAD AND INSTALL SUB-BASE. INSTALL SOIL AMENDMENT WITHIN SWALE 1 AND STABILIZE WITH PERMANENT LINING AS SPECIFIED ON THE PLANS. 23. STABILIZE REMAINING DISTURBED AREAS WITH TEMPORARY SEEDING AND MULCH IN LAWN AREAS. NO MORE THAN 15,000

# C. SITE IMPROVEMENTS-INDIVIDUAL LOTS

27. SILT SOCK #1 SHALL BE REMOVED.

24. THE LIMIT OF DISTURBANCE (LOD) SHALL BE MARKED WITH SURVEY STAKES, POSTS AND ROPE, CONSTRUCTION FENCE OR SOME OTHER ACCEPTABLE MATERIAL PRIOR TO DISTURBANCE ACTIVITIES. CONSTRUCTION FENCE SHALL BE USED IN WOODED AREAS TO ACT AS TREE PROTECTION FENCE AND TO DELINEATE THE EXTENT OF EARTH MOVING AREAS. THE AREA OF THE RAIN

SQUARE FEET OF DISTURBED AREA SHALL REACH FINAL GRADE BEFORE INITIATING STABILIZATION OPERATIONS.

INDIVIDUAL LOT CONSTRUCTION CAN OCCUR SIMULTANEOUSLY OR IN ANY ORDER.

GARDEN SHALL BE NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THE AREA SHALL BE PROTECTED BY USING TAPE, FENCING OR OTHER SUITABLE METHOD. 25. THE CONSTRUCTION ENTRANCE SHALL BE ESTABLISHED WHERE SHOWN ON THE PLAN, INCLUDING THE TIRE WASH AREA. THIS AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE MONTGOMERY COUNTY CONSERVATION DISTRICT TO SHALL BE THE ONLY ENTRANCE AND EXIT FROM THE LOT FOR THE CONSTRUCTION VEHICLES. 26. THE SILT SOCK #6 SHALL BE INSTALLED WHERE SHOWN ON THE PLAN, SILT SOCK MUST BE PROPERLY FUNCTIONING BEFORE THE CONSTRUCTION OF TRIBUTARY IMPROVEMENTS

28. INSTALL SEWER LATERAL CONNECTION TO EXISTING SEWAGE ABSORPTION AREA, AVOIDING TREE REMOVAL. FOLLOW UTILITY LINE EXCAVATION PROCEDURES. 29 INSTALL WELL AND WATER LATERAL CONNECTION AVOID TREE REMOVAL FOLLOW LITELITY LINE EXCAVATION PROC 30. STRIP THE TOPSOIL FROM CONSTRUCTION AREA AND PLACE WHERE SHOWN ON THE PLAN. ANY EXCESS TOPSOIL MAY BE HAULED OFFSITE TO A FACILITY WITH AN APPROVED EROSION CONTROL PLAN. ANY REQUIRED FILL IMPORTED TO THE SITE

MOUNTARI F

BERM (6 IN. MIN.)\*

2017-06-06

10-25-16

10-21-15

DATE

JCE


WJD

WJD

BY

BDB

BDB



\* MOUNTABLE BERM USED TO PROVIDE PROPER COVER FOR PIPE

REMOVE TOPSOIL PRIOR TO INSTALLATION OF ROCK CONSTRUCTION ENTRANCE. EXTEND ROCK OVER FULL WIDTH OF ENTRANCE.

RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR TO ENTERING ROCK CONSTRUCTION ENTRANCE.

COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND PROPER PIPE

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY 50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK, WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

# STANDARD CONSTRUCTION DETAIL #3-1 **ROCK CONSTRUCTION ENTRANCE**

PER MONTGOMERY COUNTY CONSERVATION DISTRICT 3/1/16, PENNDOT 12/5/16, GILMORE 12/6/16, MCMAHON

PER GILMORE&ASSOCIATES, INC 6/5/2015, KMS DESIGN GROUP, LLC 6/4/2015, MCMAHON ASSOCIATES, INC.

6/5/2015, AND MONTGOMERY COUNTY PLANNING COMMISSION 6/30/2015 REVIEW LETTERS.

PER GILMORE&ASSOCIATES, INC 3/14/16, KMS DESIGN GROUP, LLC 3/16/16, MCMAHON ASSOCIATES, INC. 2/11/16

2/12/16, KMS DESIGN 12/8/16 REVIEW LETTERS

SHALL MEET THE CLEAN FILL REQUIREMENTS AND THE SITE SHALL HAVE AN APPROVED EROSION CONTROL PLAN. 31. CONSTRUCT HOUSE AND DRIVEWAY.

32. INSTALL INFILTRATION BERM #4 (IB-4) 33. STABILIZE DISTURBED AREAS WITH TEMPORARY SEEDING AND MULCH IN LAWN AREAS. NO MORE THAN 15,000 SQUARE FEET

EARTH DISTURBANCE ACTIVITY INCLUDING BMPS TO AVOID, MINIMIZE OR MITIGATE POTENTIAL POLLUTION FROM THERMAL OF DISTURBED AREA SHALL REACH FINAL GRADE BEFORE INITIATING STABILIZATION OPERATIONS. IMPACTS.

WHEN ALL OF THE DISTURBANCES ON LOT 1 ARE COMPLETELY STABILIZED (A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER), ALL TEMPORARY BMP'S SHOULD BE REMOVED FROM THE SITE (INCLUDING ALL SILTSOXX) AND ANY DISTURBANCE CREATED WHEN REMOVING THEM SHALL IMMEDIATELY BE PERMANENTLY SEEDED AND MULCHED. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING GERMINATING SEASON.

24. THE LIMIT OF DISTURBANCE (LOD) SHALL BE MARKED WITH SURVEY STAKES, POSTS AND ROPE, CONSTRUCTION FENCE OR SOME OTHER ACCEPTABLE MATERIAL PRIOR TO DISTURBANCE ACTIVITIES. CONSTRUCTION FENCE SHALL BE USED IN WOODED AREAS TO ACT AS TREE PROTECTION FENCE AND TO DELINEATE THE EXTENT OF EARTH MOVING AREAS. THE AREA OF THE RAIN GARDEN SHALL BE NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THE AREA SHALL BE PROTECTED BY USING TAPE, FENCING OR OTHER SUITABLE METHOD.

25. THE CONSTRUCTION ENTRANCE SHALL BE ESTABLISHED WHERE SHOWN ON THE PLAN, INCLUDING THE TIRE WASH AREA, THIS SHALL BE THE ONLY ENTRANCE AND EXIT FROM THE LOT FOR THE CONSTRUCTION VEHICLES. 26. INSTALL THE TEMPORARY RIP RAP APRON, SLOPE PIPE, AND DIVERSION BERM-1 (TDB-1).

27. THE SILT SOCK #4 AND DOWNSLOPE OF TOPSOIL STOCKPILE SHALL BE INSTALLED WHERE SHOWN ON THE PLAN. SILT SOCK MUST BE PROPERLY FUNCTIONING BEFORE THE CONSTRUCTION OF TRIBUTARY IMPROVEMENTS. 28. CLEAR AND GRUB THE CONSTRUCTION AREAS ON LOT 2

29. STRIP THE TOPSOIL FROM THE CONSTRUCTION AREA AND PLACE WHERE SHOWN ON THE PLAN. ANY EXCESS TOPSOIL MAY BE HAULED OFFSITE TO A FACILITY WITH AN APPROVED FROSION CONTROL PLAN. ANY REQUIRED FILL IMPORTED TO THE SITE SHALL MEET THE CLEAN FILL REQUIREMENTS AND THE SITE SHALL HAVE AN APPROVED EROSION CONTROL PLAN. 30, ROUGH GRADE THE LOT. 31. CONSTRUCT THE PRIMARY ABSORPTION AREA AND INSTALL SEWER LATERAL CONNECTION TO EXISTING SEWAGE ABSORPTION

AREA, AVOIDING TREE REMOVAL. FOLLOW UTILITY LINE EXCAVATION PROCEDURES FOR LATERAL CONSTRUCTION. 32, INSTALL WELL AND WATER LATERAL CONNECTION, AVOID TREE REMOVAL, FOLLOW UTILITY LINE EXCAVATION PROCEDURES 33. CONSTRUCT RAIN GARDEN 2 ACCORDING TO THE RAIN GARDEN INSTALLATION PROCEDURES. THE AREA OF THE RAIN GARDEN SHALL BE NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THE AREA SHALL BE PROTECTED BY USING TAPE, FENCING OR OTHER SUITABLE METHOD.

34. INSTALL SWALES 3 AND 4. 35. CONSTRUCT THE HOUSE AND DRIVEWAY.

36. INSTALL INFILTRATION BERMS #1 AND #2 (IB-1 & IB-2)

37. CLEAR AND GRUB THE CONSTRUCTION AREAS ON LOT 3.

43. CONSTRUCT THE HOUSE AND DRIVEWAY.

CHEDULE A FINAL INSPECTION.

REPLACED IF IT IS CLOGGED.

37. STABILIZE DISTURBED AREAS WITH TEMPORARY SEEDING AND MULCH IN LAWN AREAS. NO MORE THAN 15,000 SQUARE FEET OF DISTURBED AREA SHALL REACH FINAL GRADE BEFORE INITIATING STABILIZATION OPERATIONS.

WHEN ALL OF THE DISTURBANCES ON LOT 2 ARE COMPLETELY STABILIZED (A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER), ALL TEMPORARY BMP'S SHOULD BE REMOVED FROM THE SITE (INCLUDING ALL SILTSOXX) AND ANY DISTURBANCE CREATED WHEN REMOVING THEM SHALL IMMEDIATELY BE PERMANENTLY SEEDED AND MULCHED. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY **DURING GERMINATING SEASON.** 

34. THE LIMIT OF DISTURBANCE (LOD) SHALL BE MARKED WITH SURVEY STAKES, POSTS AND ROPE, CONSTRUCTION FENCE OR SOME OTHER ACCEPTABLE MATERÍAL PRIOR TO DISTURBANCE ACTIVITIES. CONSTRUCTION FENCE SHALL BE USED IN WOODED AREAS TO ACT AS TREE PROTECTION FENCE AND TO DELINEATE THE EXTENT OF EARTH MOVING AREAS. THE AREA OF THE RAIN GARDEN SHALL BE NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THE AREA SHALL BE PROTECTED BY USING TAPE, FENCING OR OTHER SUITABLE METHOD. 35. THE CONSTRUCTION ENTRANCE SHALL BE ESTABLISHED WHERE SHOWN ON THE PLAN, INCLUDING THE TIRE WASH AREA. THIS

SHALL BE THE ONLY ENTRANCE AND EXIT FROM THE LOT FOR THE CONSTRUCTION VEHICLES. 36. THE SILT SOCKS #5 AND #7 SHALL BE INSTALLED WHERE SHOWN ON THE PLAN. SILT SOCK MUST BE PROPERLY FUNCTIONING BEFORE THE CONSTRUCTION OF TRIBUTARY IMPROVEMENTS.

38. STRIP THE TOPSOIL FROM THE CONSTRUCTION AREA AND PLACE WHERE SHOWN ON THE PLAN. ANY EXCESS TOPSOIL MAY BE HAULED OFFSITE TO A FACILITY WITH AN APPROVED EROSION CONTROL PLAN. ANY REQUIRED FILL IMPORTED TO THE SITE SHALL MEET THE CLEAN FILL REQUIREMENTS AND THE SITE SHALL HAVE AN APPROVED EROSION CONTROL PLAN. 39. ROUGH GRADE THE LOT. 40. CONSTRUCT THE PRIMARY ABSORPTION AREA AND INSTALL SEWER LATERAL CONNECTION TO EXISTING SEWAGE ABSORPTION

AREA, AVOIDING TREE REMOVAL. FOLLOW UTILITY LINE EXCAVATION PROCEDURES FOR LATERAL CONSTRUCTION. 41. INSTALL WELL AND WATER LATERAL CONNECTION, AVOID TREE REMOVAL. FOLLOW UTILITY LINE EXCAVATION PROCEDURES. 42. CONSTRUCT RAIN GARDEN 3 ACCORDING TO THE RAIN GARDEN INSTALLATION PROCEDURES. THE AREA OF THE RAIN GARDEN SHALL BE NOT BE COMPACTED OR RECEIVE EXCESSIVE HEAVY EQUIPMENT TRAFFIC. THE AREA SHALL BE PROTECTED BY USING TAPE, FENCING OR OTHER SUITABLE METHOD.

44. INSTALL INFILTRATION BERM #3 (IB-3) 45 STARILIZE DISTURBED AREAS WITH TEMPORARY SEEDING AND MULCH IN LAWN AREAS, NO MORE THAN 15,000 SOUARE FEET OF DISTURBED AREA SHALL REACH FINAL GRADE BEFORE INITIATING STABILIZATION OPERATIONS.

WHEN ALL OF THE DISTURBANCES ON LOT 3 ARE COMPLETELY STABILIZED (A MINIMUM OF 70% UNIFORM PERENNIAL VEGETATIVE COVER), ALL TEMPORARY BMP'S SHOULD BE REMOVED FROM THE SITE (INCLUDING ALL SILTSOXX) AND ANY DISTURBANCE CREATED WHEN REMOVING THEM SHALL IMMEDIATELY BE PERMANENTLY SEEDED AND MULCHED. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED

X. 102.4(B)(5)(X) - A MAINTENANCE PROGRAM WHICH PROVIDES FOR INSPECTION OF BMP'S ON A WEEKLY BASIS AND AFTER FACH MEASUREABLE RAINFALL EVENT, INCLUDING THE REPAIR OF THE BMP'S TO ENSURE EFFECTIVE AND EFFICIENT OPERATION.

MAINTENANCE PROGRAM I. THE CONTRACTOR AND/OR OWNER SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION CONTROL FACILITIES.

2. ALL EROSION CONTROL FACILITIES SHALL BE INSPECTED AFTER EACH RAINFALL EVENT AND WEEKLY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND IN WORKING CONDITION. ANY DAMAGED FACILITY SHALL BE REPAIRED IMMEDIATELY. 3. SEEDED AREAS THAT HAVE ERODED SHALL BE FILLED AND GRADED AS NECESSARY AND THEN RESEEDED AND MULCHED 4. THE INSPECTIONS AND MAINTENANCE SHALL CONTINUE AFTER EACH SIZABLE STORM EVENT UNTIL SIGNS OF EROSION ARE GONE, INSPECTIONS AND NECESSARY CLEANING AND MAINTENANCE SHALL BE PERFORMED MONTHLY THEREAFTER.

5. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE

INSPECTION. 6.E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT. 7. THE SILT THAT HAS ACCUMULATED SHALL BE REMOVED FROM THE EROSION CONTROL STRUCTURE, ALLOWED TO DRY AND THEN IT CAN BE USED AS FILL WHERE NEEDED ON THE SITE, INSPECT THE INLET PROTECTION, ROCK FILTER OUTLETS, SILT SOXXTM. SEDIMENT TRAPS AND SWALES WEEKLY AND AFTER EACH STORM EVENT. THE FILTER MATERIAL SHALL BE CLEANED AND/OR

CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF

LOCAL ORDINANCES SHALL BE FOLLOWED 9. ANY TRASH THAT IS REMOVED FROM THE EROSION CONTROL STRUCTURES SHALL BE DISPOSED IN ACCORDANCE WITH LOCAL STATE AND FEDERAL REGULATIONS. THE INSTALLATION AND MAINTENANCE OF THE TEMPORARY CONTROL FACILITIES WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE TEMPORARY CONTROLS WILL BE MAINTAINED IN ACCORDANCE WITH THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION REGULATIONS. 10. THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION REGULATIONS REQUIRE A 70% UNIFORM EROSION

RESISTANT PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO

RESIST ACCELERATED FROSION OVER ALL DISTURBED AREAS BE ESTABLISHED BEFORE THE SITE IS CONSIDERED PERMANENTLY

8. THE VEGETATION SHALL BE MOWED AS NECESSARY TO MAINTAIN A NEAT APPEARANCE AND DISCOURAGE WEED GROWTH. THE

MOVEMENTS. UNTIL SUCH TIME AS THE STANDARD IS ACHIEVED, INTERIM STABILIZATION AND TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES AND FACILITIES THAT ARE USED TO TREAT THE RUNOFF SHALL REMAIN IN PLACE. 11. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING THE TEMPORARY EROSION CONTROLS AFTER THE SITE IS PERMANENTLY STABILIZED WITH VEGETATION. THE CONTRACTOR SHALL STABILIZE ANY AREAS DISTURBED DURING THE REMOVAL OF THE EROSION CONTROL FACILITIES.

STABILIZED, CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER

12. AFTER THE SITE IS PERMANENTLY STABILIZED, THE PROPERTY OWNER AND HOMEOWNERS ASSOCIATION SHALL PERIODICALLY CHECKTHE GRADED AREAS AND SWALES FOR ANY DEVELOPING EROSION PROBLEMS. ANY DAMAGED AREAS SHALL BE REPAIRED

XI. 102.4(B)(5)(XI) - PROCEDURES WHICH ENSURE THAT THE PROPER MEASURES FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE WILL BE UNDERTAKEN IN ACCORDANCE WITH DEPARTMENT REGULATIONS. THE SITE WILL NOT BE USED TO STORE ANY CHEMICALS, SOLVENTS OR OTHER HAZARDOUS WASTE OR MATERIALS WITH THE

POTENTIAL TO CAUSE ACCIDENTAL POLLUTION DURING EARTH DISTURBANCE ACTIVITIES. PROJECT CONSTRUCTION WASTE

WILL BE REMOVED FROM THE SITE. SEDIMENT REMOVED FROM THE EROSION CONTROL MEASURES/FACILITIES SHALL BE

DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOOD PLAINS AND DRAINAGE SWALES AND IMMEDIATELY STABILIZED OR PLACED ON TOPSOIL STOCKPILES. NO MATERIAL MAY BE REMOVED FROM THIS PROJECT WITHOUT AN EROSION CONTROL PLAN APPROVED BY THE LOCAL

SEAL

CONSERVATION DISTRICT FOR THE DISPOSAL SITE. TEMPORARY AND PERMANENT CONTROL MEASURES AND FACILITIES MUST BE MAINTAINED DURING THE PROGRESS OF THE WORK AT THE SITE. THIS WILL BE DONE BY IMPLEMENTING A PROGRAM OF PROPER DISPOSAL OF MATERIALS AND FREQUENT REMOVAL OF SOLID MATERIALS FROM THE EROSION CONTROL FACILITIES.

XII. 102.4(B)(5)(XII) IDENTIFICATION OF THE NATURAL OCCURRING GEOLOGIC FORMATIONS OR SOIL CONDITIONS THAT MAY HAVE THE POTENTIAL TO CAUSE POLLUTION DURING EARTH DISTURBANCE ACTIVITIES AND INCLUDE BMPS TO AVOID OR MINIMIZE

WOODED AREAS OUTSIDE OF THE PROPOSED EARTHMOVING SHALL HELP MITIGATE POTENTIAL THERMAL IMPACTS. DURING EARTHMOVING ACTIVITIES THE POTENTIAL FOR THERMAL IMPACTS IS MINIMAL DUE THE PRIMARY BMP CONTROLS BEING COMPOST FILTER SOCKS PLACED IN SHADED WOODED AREAS AND NOT SEDIMENT TRAPS/BASINS WHICH STORE WATER AND ALLOW IT TO INCREASE IN TEMPERATURE THROUGH EXPOSURE TO SUNLIGHT.

THERE ARE NO GEOLOGIC FORMATIONS OR SOIL CONDITIONS OF THE TYPE OF CONCERN.


XIII.102.4(B)(5)(XIII) IDENTIFICATION OF POTENTIAL THERMAL IMPACTS TO SURFACE WATERS OF THIS COMMONWEALTH FROM THE


INFILTRATION BERMS PRIOR TO DISCHARGE TO CHANNELS AND WETLANDS. THESE BMP'S WILL INFILTRATE AND

PORTIONS OF PROPOSED AND EXISTING IMPERVIOUS SURFACES WILL DRAIN TO AMENDED SOIL, RAINGARDENS, AND

EVAPOTRANSPIRATE STORMWATER TO PREVENT WARMING OF RUNOFF AS A RESULT OF THIS DEVELOPMENT. PROTECTION OF

POTENTIAL POLLUTION AND ITS IMPACTS FROM SUCH FORMATIONS.





THICK. LENGTH SIZE | Rt | Al WIDTH | R-\_ | (IN) | (FT) | (FT) | (IN) At w 3 | 8 | 8 | 3.75 | 11.75


ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.


ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

EXTEND RIPRAP ON BACK SIDE OF APRON TO AT LEAST 1/2 DEPTH OF PIPE ON BOTH SIDES TO PREVENT SCOUR AROUND THE PIPE.

ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE

STANDARD CONSTRUCTION DETAIL #9-2 RIPRAP APRON AT PIPE OUTLET NO FLARED ENDWALL NOT TO SCALE





# SECTION VIEW

FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL

FABRIC WIDTH SHALL BE 30 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES. SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE.

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.

ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET (STANDARD CONSTRUCTION DETAIL # 4-6).

> STANDARD CONSTRUCTION DETAIL #4-7 STANDARD SILT FENCE (18" HIGH)

> > NOT TO SCALE

EROSION CONTROL NARRATIVE & DETAILS

DESIGN

FDEV SUBDIVISION

NEW HANOVER TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA



1860 WEAVERTOWN ROAD, SUITE 100 **DOUGLASSVILLE, PA 19518** 14-146 PHONE: 610-689-8021 FAX: 610-689-4538 CHKD. BY ES314146 BDB DRAWN BY CHKD. BY SHEET NO. WJD SCALE 10/29/15

1150 FIRST AVE STE 920 KING OF PRUSSIA, PA 19406

CLIENT

FDEV LLC

NGINEERING LLC | DATE

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

NOTES:

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

# STANDARD CONSTRUCTION DETAIL #3-16 PUMPED WATER FILTER BAG

NOT TO SCALE

CHANNEL

∠TOP OF RIPRAP

∼3 FT. MIN.

DEPTH

∠DOWNSTREAM


SIDE SLOPES TO VARY FROM


2:1 AT PIPE OUTLETS TO

EXISTING CHANNEL SIDE SLOPES AT END OF APRON

CHANNEL INVERT

-SLOPE POSITIVE





SLOPE PIPE NO.	OUTLET PROTECTION TYPE	RIPRAP SIZE OR MATERIAL	APRON LENGTH (FT)	APRON WIDTH (FT)
1	RIPRAP	R-3	6	9

NOTES:


SHALL BE REMOVED FROM THE INLET IMMEDIATELY.

THE MAXIMUM DISTANCE BETWEEN ANCHOR STAKES SHALL BE 10 FEET. TRANSVERSE BERM SHALL BE USED WHENEVER TEMPORARY SLOPE PIPE IS NOT LOCATED AT LOW POINT. SLOPE PIPES SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. ANY ACCUMULATED SEDIMENT

DAMAGED PIPE SECTIONS SHALL BE REPLACED WITHIN 24 HOURS. LEAKING CONNECTIONS SHALL BE REPAIRED

# STANDARD CONSTRUCTION DETAIL #6-5 TEMPORARY SLOPE PIPE

NOT TO SCALE



### INITIAL TOP END TOP WIDTH WIDTH BOTTOM THICK. LENGTH SIZE WIDTH WIDTH | SLOPES | (IN) (FT) (AT ENDWALL) (FT) (AT ENDWALL) (FT) (FT)

GEOTEXTILE/

<u>PLAN VIEW</u>

SECTION VIEW

SECTION A-A

GEOTEXTILE/

RIPRAP TO EXTEND TO-

ANTICIPATED MAX. FLOW

Q FOR PIPE DISCHARGE

DEPTH BASED ON DESIGN

CHANNEL

NOTES: ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY

ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

# STANDARD CONSTRUCTION DETAIL #9-3 RIPRAP APRON AT PIPE OUTLET TO AN EXISTING CHANNEL


NOTES: ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.

# STANDARD CONSTRUCTION DETAIL #9-1 RIPRAP APRON AT PIPE OUTLET

ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE

APRON SHALL BE REPLACED IMMEDIATELY.

2017-06-06 PER MONTGOMERY COUNTY CONSERVATION DISTRICT 3/1/16, PENNDOT 12/5/16, GILMORE 12/6/16, MCMAHON 12/12/16, KMS DESIGN 12/8/16 REVIEW LETTERS JCE PER GILMORE&ASSOCIATES, INC 3/14/16, KMS DESIGN GROUP, LLC 3/16/16, MCMAHON ASSOCIATES, INC. 2/11/16 10-25-16 WJD BDB PER GILMORE&ASSOCIATES, INC 6/5/2015, KMS DESIGN GROUP, LLC 6/4/2015, MCMAHON ASSOCIATES, INC. BDB 10-21-15 MJD 6/5/2015, AND MONTGOMERY COUNTY PLANNING COMMISSION 6/30/2015 REVIEW LETTERS. DATE APP. BY



SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.

COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.

TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.


COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.

BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S

UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

## STANDARD CONSTRUCTION DETAIL #4-1 COMPOST FILTER SOCK

NOT TO SCALE



NOTES:

FABRIC SHALL HAVE THE MINIMUM PROPERTIES AS SHOWN IN TABLE 4.3 OF THE PA DEP EROSION CONTROL MANUAL. FABRIC WIDTH SHALL BE 42 IN. MINIMUM. STAKES SHALL BE HARDWOOD OR EQUIVALENT STEEL (U OR T) STAKES. AN 18 IN. SUPPORT STAKE SHALL BE DRIVEN 12 IN. MINIMUM INTO UNDISTURBED GROUND.

SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE.

ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK

FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.

# STANDARD CONSTRUCTION DETAIL #4-8 REINFORCED SILT FENCE (30" HIGH)

NOT TO SCALE

SEAL

FDEV LLC 1150 FIRST AVE STE 920 KING OF PRUSSIA, PA

CLIENT

19406

DESIGN GRADE AND OVERCUT CHANNEL 2 IN. TO ALLOW BULKING DURING SEED ANCHOR TRENCH BED PREPARATION INTERMITTENT CHECK SLOT SHINGLE-LAP SPLICED ENDS OR BEGIN NEW ROLL IN AN INTERMITTENT CHECK SLOT MIN. SHINGLE LAP=6 IN. PREPARE SOIL AND APPLY SEED BEFORE INSTALLING BLANKETS, MATS, OR OTHER # TEMPORARY CHANNEL LINER SYSTEM. ANCHOR TRENCH (LOOKING DOWNSTREAM) CHANNEL CROSS-SECTION

EXCAVATE CHANNEL TO

6 IN. MIN.

/SOIL BACKFILL

\* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION


	CHANNEL NO.	STATIONS	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *
	1	ALL	2	0.7	37	25	25	ECS-1
	2	ALL	2	0.8	6.8	3	3	ECS-1
NOTES:	3	ALL	2	0.8	6.8	3	3	ECS-1
NOTES:	4	ALL	1.5	0.8	6.8	3	3	ECS-1
ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL								

CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION. SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS


NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

# STANDARD CONSTRUCTION DETAIL #6-1

**VEGETATED CHANNEL** NOT TO SCALE



# OUTLET CROSS-SECTION



UP-SLOPE FACE

NOTES:

ANCHOR TRENCHES.

A ROCK FILTER OUTLET SHALL BE INSTALLED WHERE FAILURE OF A SILT FENCE OR STRAW BALE BARRIER HAS OCCURRED DUE TO CONCENTRATED FLOW. ANCHORED COMPOST LAYER SHALL BE USED ON UPSLOPE FACE IN HQ AND EV WATERSHEDS.

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE OUTLET. STANDARD CONSTRUCTION DETAIL #4-6


EROSION CONTROL DETAILS

**ROCK FILTER OUTLET** NOT TO SCALE

SUBJECT

FDEV SUBDIVISION

# NEW HANOVER TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA





NOT TO SCALE

WITH FLARED END SECTION OR ENDWALL NOT TO SCALE


SEAL

10 OF 13 10/29/15









LEGEND

EX. BOUNDARY

0 30 60 120 240 SCALE:1"= 60'

SUBJECT

FDEV LLC 1150 FIRST AVE STE 920 KING OF PRUSSIA, PA 19406

CLIENT

AERIAL PLAN


FDEV SUBDIVISION

NEW HANOVER TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

	FINAL PLAN - PHASE 1	2017-06-06	WJD	BDB
	PER MONTGOMERY COUNTY CONSERVATION DISTRICT 3/1/16, PENNDOT 12/5/16, GILMORE 12/6/16, MCMAHON 12/12/16, KMS DESIGN 12/8/16 REVIEW LETTERS	1-12-17	JCE	BDB
	PER GILMORE&ASSOCIATES, INC 3/14/16, KMS DESIGN GROUP, LLC 3/16/16, MCMAHON ASSOCIATES, INC. 2/11/16 REVIEW LETTERS.	10-25-16	WJD	BDB
	PER GILMORE&ASSOCIATES, INC 6/5/2015, KMS DESIGN GROUP, LLC 6/4/2015, MCMAHON ASSOCIATES, INC. 6/5/2015, AND MONTGOMERY COUNTY PLANNING COMMISSION 6/30/2015 REVIEW LETTERS.	10-21-15	WJD	BDB
•	REVISION	DATE	BY	APP.

	1
	D
Boyer	D
ENGINEERING LLC	D

1860 WEAVERTOWN ROAD, SUITE 100 DOUGLASSVILLE, PA 19518 PHONE: 610-689-8021 FAX: 610-689-4538		PROJECT NO. 14—146
		DWG. NO.
DESIGN	CHKD. BY	
BDB		AP114146
DRAWN BY	CHKD. BY	
WJD		SHEET NO.
DATE	SCALE	12 OF 13
4/22/15	1"=60'	



LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY, BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE


THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

## STANDARD CONSTRUCTION DETAIL #3-16 PUMPED WATER FILTER BAG

NOT TO SCALE



GRUBBING SHALL NOT TAKE PLACE WITHIN 50 FEET OF TOP-OF-BANK UNTIL ALL MATERIALS REQUIRED TO

COMPLETE CROSSING ARE ON SITE AND PIPE IS READY FOR INSTALLATION.

NOTES:

14. SPACING OF CULVERTS SHALL BE A MINIMUM OF TEN (10) FEET ON CENTER. 15. DEPTH OF FILL COVERING CULVERTS SHALL NOT EXCEED TWELVE (12) INCHES.

FEET IN LENGTH AND 0.1 ACRE OF DISTURBANCE.

THE BERKS COUNTY CONSERVATION DISTRICT.

ACTIVITIES ON THIS PROPERTY.

BYPASS PUMP INTAKE SHALL BE MAINTAINED A SUFFICIENT DISTANCE FROM THE BOTTOM TO PREVENT PUMPING OF CHANNEL BOTTOM MATERIALS.

TRENCH PLUGS SHALL BE INSTALLED WITHIN THE TRENCH ON BOTH SIDES OF THE STREAM CHANNEL (STANDARD CONSTRUCTION DETAIL #13-4).

WATER ACCUMULATING WITHIN THE WORK AREA SHALL BE PUMPED TO A PUMPED WATER FILTER BAG OR SEDIMENT TRAP PRIOR TO DISCHARGING INTO ANY SURFACE WATER.

HAZARDOUS OR POLLUTANT MATERIAL STORAGE AREAS SHALL BE LOCATED AT LEAST 100 FEET BACK FROM THE TOP OF STREAMBANK.


ALL EXCESS EXCAVATED MATERIAL SHALL BE IMMEDIATELY REMOVED FROM THE STREAM CROSSING AREA. ALL DISTURBED AREAS WITHIN 50 FEET OF TOP-OF-BANK SHALL BE BLANKETED OR MATTED WITHIN 24 HOURS


OF INITIAL DISTURBANCE FOR MINOR STREAMS OR 48 HOURS OF INITIAL DISTURBANCE FOR MAJOR STREAMS UNLESS OTHERWISE AUTHORIZED.


APPROPRIATE STREAMBANK PROTECTION SHALL BE PROVIDED WITHIN THE CHANNEL.

# STANDARD CONSTRUCTION DETAIL #13-2 TYPICAL UTILITY LINE STREAM CROSSING WITH PUMP BYPASS


NOT TO SCALE







# R=20.00 245.71. EXISTING ROW EXISTING EDGE OF PAVING M.E1.85.255 21.688



CH. 105 GENERAL PERMIT SHEET

FDEV LLC 1150 FIRST AVE STE 920 KING OF PRUSSIA, PA 19406

CLIENT

SEAL


SEAL


FDEV SUBDIVISION

SUBJECT

NEW HANOVER TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

1860 WEAVERTOWN ROAD, SUITE 100 | **DOUGLASSVILLE, PA 19518** 14 - 146PHONE: 610-689-8021 FAX: 610-689-4538 DWG. NO. DESIGN CHKD. BY GP114146 BDB DRAWN BY CHKD. BY SHEET NO. ENGINEERING LLC | DATE SCALE 13 OF 13 11/19/15





TELEPHONE (717)783-8946.

9. MATS, PADS, AND OTHER SIMILAR DEVICES SHALL BE USED WHERE CROSSINGS OF WETLAND AREAS BY CONSTRUCTION EQUIPMENT CANNOT BE AVOIDED. ORIGINAL GRADES THROUGH WETLANDS MUST BE RESTORED AFTER TRENCHING AND BACKFILLING, ANY EXCESS FILL MATERIAL MUST BE REMOVED FROM THE WETLANDS AND NOT RESPREADS ON—SITE. MOUNDING OF FILL MATERIAL TO ALLOW FOR SETTLEMENT IN THE TRENCH WILL BE PERMITTED IN ACCORDANCE WITH THE BEST CONSTRUCTION METHODS.

10. DEPOSITION OF DREDGED OR EXCAVATED MATERIALS AND ALL EARTHWORK OPERATIONS WILL BE CARRIED OUT IN SUCH A WAY AS TO MINIMIZE EROSION OF THE MATERIAL AND PRECLUDE ITS ENTERING INTO ANY WETLAND ADJACENT TO THE UTILITY CROSSING. 11. UTILITY LINE CROSSINGS OF STREAMS SHOULD BE ACCOMPLISHED SO THAT THE LINE IS AT A RIGHT ANGLE TO THE STREAM WHERE

DRY" BY INSTALLING SANDBAG AND PLASTIC DAMS AND PIPING STREAM FLOW THROUGH THE AFFECTED AREA. FROM THE FISH AND BOAT COMMISSION UNDER PENNSYLVANIA FISH AND BOAT CODE PA. C.S. \$2906 (RELATING TO PERMITS FOR

14. AS A CONDITION OF USE OF THIS GENERAL PERMIT, AND OF THE OWNER'S AUTHORITY TO CONDUCT THE ACTIVITIES AUTHORIZED BY DEPARTMENT, WITHOUT ADVANCE NOTICE OR A SEARCH WARRANT, AT ANY REASONABLE TIME AND UPON PRESENTATION OF CONSTRUCTED, OPERATED OR MAINTAINED. THE AUTHORIZATION AND CONSENT SHALL INCLUDE CONSENT

2 BAG MIN. HEIGHT ABOVE NORMAL BASE FLOW STACKED SANDBAGS OPTION SANDBAG TO HOLD IMPERVIOUS LINER IN PLACE IMPERVIOUS LINER EXTENDED TO WORK AREA STREAM BOTTOM AND SECURED WITH SANDBAGS JERSEY BARRIER-SANDBAG (TYP.) NORMAL STREAM FLOW OPTIONAL SANDBAG PLATFORM JERSEY BARRIER OPTION

# STANDARD CONSTRUCTION DETAIL #3-15 SANDBAG DIVERSION DAM OR COFFERDAM

NOT TO SCALE

IMPERVIOUS MEMBRANE

GENERAL PERMIT FOR MINOR ROAD CROSSING(GP-7) NOTES

THE MINOR ROAD CROSSING SHALL COMPLY WITH THE FOLLOWING CONDITIONS:

1. THE CONSTRUCTION OF A MINOR ROAD CROSSING SHALL BE COMPLETED WITHIN THREE (3) YEARS OF THE DATE OF THE DEPARTMENT'S ACKNOWLEDGEMENT LETTER. IF ALL CONSTRUCTION IS NOT COMPLETED WITHIN THIS TIME FRAME, THE OWNER SHALL REMIVE ALL OF THE MINOR ROAD CROSSING AND RESTORE THE WATERCOURSE AND FLOODPLAIN TO THEIR FORMER CONDITIONS. MINOR ROAD CROSSINGS SHALL NOT CREATE OR CONSTITUTE A RISK OF LIFE, PROPERTY, OR THE ENVIRONMENT

3. NO FILL SHALL BE PLACED IN ANY FLOODWAY, WATERCOURSE, OR BODY OF WATER, INCLUDING APPROACHES TO THE MINOR ROAD CROSSING, EXCEPT AS SPECIFICALLY AUTHORIZED IN THIS GENERAL PERMIT. 4. EACH MINOR ROAD CROSSING SHALL BE CONSTRUCTED IN SUCH A MANNER SO THAT THERE IS NO INTERFERENCE WITH THE

THE CROSSING SHALL BE DESIGNED TO PREVENT THE RESTRICTION OF AND TO WITHSTAND EXPECTED HIGH FLOWS. CULVERT CROSSINGS SHALL HAVE A WATERWAY OPENING SUFFICIENT TO ADEQUATELY DISCHARGE, AT A MINIMUM, THE BANK-FULL FLOW OF THE WATERCOURSE OR STREAM. THE WATERWAY OPENING SHALL BE LARGE ENOUGH TO MINIMIZE AND CONFINE ANY BACKWATER TO THE OWNER'S PROPERTY.

. HEADWALLS, WINGWALLS, AND RIPRAP SHALL BE INSTALLED FOR BRIDGES AND CULVERTS AS REQUIRED TO PASS FLOOD FLOWS WITHOUT LOSS OF STABILITY. 8. CULVERTS SHALL NOT INCREASE VELOCITY OR DIRECT FLOW SO AS TO RESULT IN EROSION OF STREAM BEDS AND BANKS. 9. CULVERTS SHALL BE INSPECTED BY THE OWNER ON A REGULAR BASIS TO PROVIDE FOR CONTINUED OPERATION AND MAINTENANCE

6. CULVERTS SHALL BE OF SUFFICIENT WIDTH AND SIZE SO AS NOT TO NARROW THE EXISTING STREAM CHANNEL.

DURING THE LIFETIME OF THE STRUCTURE. 10. APPROACHES TO CULVERTS SHALL SHOULD BE CONSTRUCTED AT ORIGINAL GRADES WHERE POSSIBLE. WHERE NECESSARY, DEPTH OF FILL IN THE APPROACHES SHALL BE MINIMIZED TO ALLOW OVERFLOW OF THE ROADWAY DURING PERIODS OF HIGH WATER. 11. CULVERTS INSTALLED IN STREAM CHANNELS SHALL BE ALIGNED WITH THE STREAM FLOW.

12. CULVERTS SHALL BE INSTALLED WITH THE INVERT 6 INCHES BELOW NATURAL STREAM BED SO THAT THE GRADIENT OF THE INVERT SHALL NOT DEVIATE FROM THAT OF THE NATURAL STREAM BED.

13. THE LENGTH OF THE CULVERTS INSTALLED SHALL BE ONLY THAT WHICH IS NECESSARY TO PROVIDE ADEQUATE ROAD WIDTH WITH

CONTROL. THE PROJECT SITE SHALL AT ALL TIMES BE AVAILABLE FOR INSPECTION BY AUTHORIZED OFFICERS AND EMPLOYEES OF GENERAL PERMIT FOR UTILITY LINESTREAM CROSSING (GP-5) NOTES THE UTILITY LINE STREAM CROSSING SHALL COMPLY WITH THE FOLLOWING CONDITIONS:

6. CROSSINGS OF WETLANDS SHALL BE AVOIDED IF AN ALTERNATE LOCATION IS POSSIBLE. IF THE CROSSING OF WETLANDS CANNOT BE AVOIDED, THE CROSSING MUST BE UNDERTAKEN AT THE NARROWEST POINT OF THE WETLANDS AN SHALL NOT EXCEED 100

17. THE TOTAL WETLAND IMPACT FOR ALL MINOR ROAD CROSSINGS INSTALLED BY AN OWNER ON AN INDIVIDUAL PROPERTY OR PROJECT INCLUDING PHASED PROJECTS SHALL NOT EXCEED 0.25 ACRE. A PROJECT SHALL INCLUDE THE AGGREGATE OF ALL STAGES OF

20. ANY ARCHAEOLOGICAL ARTIFACTS DISCOVERED DURING THE PERFORMANCE OF WORK AUTHORIZED UNDER THIS GENERAL PERMIT MUST BE ADEQUATELY PROTECTED AND THEIR DISCOVERY PROMPTLY REPORTED TO THE BUREAU FOR HISTORIC PRESERVATION, PENNSYLVANIA HISTORIC AND MUSEUM COMMISSION, 400 MARKET STREET, SECOND FLOOR, HARRISBURG, PA 17120-0093,

21. OWNER SHALL INVESTIGATE FOR DRINKING WATER INTAKES OR RESERVOIRS FOR PUBLIC WATER SUPPLIES AND PERMITTED PUBLIC BATHING BEACHES WITHIN FIVE (5) MILES DOWNSTREAM OF THE SITE OF THE MINOR ROAD CROSSING. WRITTEN NOTICES SHALL BE

GIVEN TO OPERATORS OF ANY SUCH INTAKES OR RESERVOIRS, OR PUBLIC BATHING BEACHES AT LEAST TEN (10) DAYS PRIOR TO

CONSTRUCTION OF THE MINOR ROAD CROSSING, OWNER MUST NOTIFY OPERATORS IMMEDIATELY AND NO LONGER THAN ONE (1) HOUR AFTER AN OCCURRENCE AT THE CROSSING SITE WHICH RESULTS IN THE RELEASE OF SUSPENDED SOLIDS AND TURBIDITY TO

22. THE OWNER SHALL REMOVE ALL OR ANY PORTION OF THE MINOR ROAD CROSSING UPON WRITTEN NOTIFICATION TO THE OWNER BY

23. THE OWNER SHALL NOTIFY THE PENNSYLVANIA FISH AND BOAT COMMISSION'S REGIONAL FIELD OFFICE MANAGER RESPONSIBLE FOR

OR IN ANY OTHER MANNER VIOLATES THE CONDITIONS OF THIS GENERAL PERMIT OR CHAPTER 105.

THE DEPARTMENT IN THE EVENT THE PROJECT IS CAUSING AN ADVERSE IMPACT ON PUBLIC HEALTH, SAFETY OR THE ENVIRONMENT

BERKS COUNTY TEN (10) DAYS PRIOR TO THE START OF CONSTRUCTION. WRITTEN NOTIFICATION IS SUGGESTED. THE PROJECT SITE

SHALL AT ALL TIMES BE AVAILABLE FOR INSPECTION BY AUTHORIZED OFFICERS AND EMPLOYEES OF THE PENNSYLVANIA FISH AND

24. WORK MUST BE DONE IN COMPLIANCE WITH CHAPTER 102 OF THE DEPARTMENT'S RULES AND REGULATIONS RELATING TO EROSION

DEVELOPMENT AND ALL PARCELS WITHIN A SUBDIVISION PLAN, WHICH ARE UNDER CONTROL OF THE REGISTRANT. 18. ALL WETLANDS IMPACTED THROUGH THE USE OF A GENERAL PERMIT MUST BE REPLACED ADJACENT TO OR IN THE IMMEDIATE PROXIMITY OF THE MINOR ROAD CROSSING AND AT A RATIO OF 1:1 FOR FUNCTION, VALUE, OR AREAL EXTENT(ACREAGE), 19. THE USE OF THIS GENERAL PERMIT SHALL NOT PREJUDICE ANY FUTURE DEPARTMENTAL DECISIONS RELATED TO REGULATED

THE MAXIMUM SIZE UTILITY LINE ALLOWED IS 36 INCHES IN DIAMETER. 2. ALL UTILITY LINES UNDER STREAMBEDS SHALL BE LOCATED SUCH THAT THERE WILL BE A MINIMUM OF THREE (3) FEET OF COVER BETWEEN THE TOP OF THE UTILITY LINE OR ENCASEMENT AND THE LOWEST POINT IN THE NATURAL CONTOUR OF THE STREAMBED, UNLESS THE UTILITY LINE IS IN ROCK, WHERE A MINIMUM COVER OF ONE (1) FOOT SHALL BE PROVIDED.

3. TRENCHES EXCAVATED FOR THE INSTALLATION OF UTILITY LINES SHALL BE THE MINIMUM WIDTH NECESSARY. AS SOON AS THE UTILITY LINE IS INSTALLED AND TESTED TO ASCERTAIN NO LEAKAGE, APPROPRIATE NEW OR PREVIOUSLY EXCAVATED BACKFILL MATERIAL SHALL BE PLACED IN THE TRENCH AND THE AREA RESTORED TO ITS ORIGINAL CONDITION AND ELEVATION AND STABILIZED. BACKFILL MATERIAL STORED IN CONNECTION WITH THE INSTALLATION MUST BE PROPERLY RETAINED OUT OF THE FLOODWAY SO AS TO PREVENT DISCHARGE, WASHINGS OR RUNOFF FROM ENTERING THE WATERWAY PRIOR TO ITS PLACEMENT AS

4. ADEQUATE MEASURES SHALL BE USED TO PREVENT SEDIMENTATION FROM THE TRENCH FROM ENTERING THE STREAM. 5. THE BACKFILLING OF THE TRENCH IN WHICH THE PIPE WILL BE LAID SHALL BE DONE SO AS TO ELIMINATE THE FORMATION OF A PERMANENT RIDGE IN THE STREAMBED.

6. DURING CONSTRUCTION ACTIVITIES, ALL PUBLIC AND PRIVATE PROPERTY INCLUDING EXISTING VEGETATION, LANDSCAPE FEATURES, AND MONUMENTS WITHIN, ALONG, AND ADJACENT TO THE WORK AREA, SHALL BE PROTECTED AND PRESERVED TO THE MAXIMUM DEGREE POSSIBLE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO, PRECAUTIONS TAKEN TO MINIMIZE DAMAGE, EROSION, INJURY, OR —DESTRUCTION: PREVENT POLLUTION: PROVIDE PROTECTION OF ALL TREES AND OTHER WOODY PLANTS: SPECIAL CARE BEING TAKEN TO PROTECT THE NATURAL VEGETATION AND SURROUNDINGS TO INCLUDE ALL NATURAL DRAINAGEWAYS, PONDS, LAKES, SWAMPS. WOODS AND FIELDS; AND STORAGE OF MATERIALS IN SUCH MANNER TO PREVENT LEACHING WHICH WOULD BE INJURIOUS TO SOILS

AND TO PLANTS. PRECAUTIONS SHOULD BE TAKEN TO PREVENT DAMAGE TO PIPES, CONDUITS, AND OTHER UNDERGROUND UTILITIES. 7. ANY ARCHAEOLOGICAL ARTIFACTS DISCOVERED DURING THE PERFORMANCE OF WORK AUTHORIZED UNDER THIS GENERAL PERMIT MUST BE ADEQUATELY PROTECTED AND THEIR DISCOVERY PROMPTLY REPORTED TO THE BUREAU FOR HISTORIC PRESERVATION, PENNSYLVANIA HISTORIC AND MUSEUM COMMISSION, 400 MARKET STREET, SECOND FLOOR, HARRISBURG, PA 17120-0093,

8. OWNER SHALL INVESTIGATE FOR DRINKING WATER INTAKES OR RESERVOIRS FOR PUBLIC WATER SUPPLIES WITHIN FIVE (5) MILES DOWNSTREAM OF THE UTILITY CROSSING. WRITTEN NOTICES SHALL BE GIVEN TO OPERATORS OF ANY SUCH INTAKES OR RESERVOIRS AT LEAST TEN (10) DAYS PRIOR TO CONSTRUCTION OF THE CROSSING. OWNER MUST NOTIFY PUBLIC AND PRIVATE WATER SUPPLY OPERATORS IMMEDIATELY AND NO LONGER THAN ONE (1) HOUR AFTER AN OCCURRENCE AT THE CROSSING SITE WHICH RESULTS IN THE RELEASE OF SUSPENDED SOLIDS AND TURBIDITY TO THE STREAM.

12. WHENEVER POSSIBLE, IN ACCORDANCE WITH THE BEST CONSTRUCTION METHODS UTILITY LINE CROSSINGS ARE TO BE MADE 'IN THE 13. PRIOR TO THE USE OF EXPLOSIVES IN A WATERCOURSE OR BODY OF WATER THE PERMITTEE SHALL SECURE A WRITTEN PERMIT USE OF EXPLOSIVES). REQUESTS SHOULD BE DIRECTED TO THE FISH AND BOAT COMMISSION, DMISION OF ENVIRONMENTAL

THIS GENERAL PERMIT, THE OWNER HEREBY AUTHORIZES AND CONSENTS TO ALLOW AUTHORIZED EMPLOYEES OR AGENTS OF THE APPROPRIATE CREDENTIALS AND WITHOUT DELAY TO HAVE ACCESS TO AND TO INSPECT ALL AREAS WHERE THE PROJECT IS REING

DETAIL OF GP5 & GP7.E

2017-06-06 PER MONTGOMERY COUNTY CONSERVATION DISTRICT 3/1/16, PENNDOT 12/5/16, GILMORE 12/6/16, MCMAHON JCE BDB 2/12/16, KMS DESIGN 12/8/16 REVIEW LETTERS PER GILMORE&ASSOCIATES, INC 3/14/16, KMS DESIGN GROUP, LLC 3/16/16, MCMAHON ASSOCIATES, INC. 2/11/16 10-25-16 WJD BDB PER GILMORE&ASSOCIATES, INC 6/5/2015, KMS DESIGN GROUP, LLC 6/4/2015, MCMAHON ASSOCIATES, INC. 10-21-15 WJD BDB 6/5/2015, AND MONTGOMERY COUNTY PLANNING COMMISSION 6/30/2015 REVIEW LETTERS.

DATE BY APP.

SERVICES (SEE "EXHIBIT A").